

PROJECT
PROPOSED PARTLY B+G+12 STORED AFFORDABLE HOUSING AT PREMISES NO. - MOUZA - BHASA, J.L. NO. - 20, L.R. DAG NO. - 483 TO 485, 489 TO 495, 497 TO 499, 513 TO 517, 727. P.S.- BISHNUPUR, DIST - 24 PGS (SOUTH).
(PARTLY REVISED SANCTION DONE VIDE FILE NO. - 558/688/Rev/KMDA, Dtd 01-04-2019.)

OWNER:
EDEN REALTY PVT. LTD.
 Director: [Signature] Director: [Signature]

SPECIFICATION:
 1. ALL DIMENSIONS ARE IN MM UNLESS IT IS MENTIONED.
 2. ALL EXTERNAL BRICK WALLS ARE 200 MM THICK AND INTERNAL 100 MM THICK.
 3. ALL BRICKWORK PLASTERING INSIDE OR OUTSIDE ARE IN THE RATIO OF 1:6 & 1:4 RESPECTIVELY AND OUTSIDE PLASTERING CONTAINS WATER PROOFING.
 4. ALL CIVIL WORKS ARE AS PER IS 456 AND ALL REINFORCEMENT AS PER IS 1176.
 5. ALL R.C.C. WORKS ARE IN THE RATIO M:2:5.
 6. ALL PRECAUTIONARY MEASURES SHALL BE TAKEN AT THE TIME OF CONSTRUCTION.
 7. DEPTH OF WATER RESERVOIR SHALL NOT BE MORE THAN THE DEPTH OF MAIN COLUMN FOUNDATION.

DOOR WINDOW SCHEDULE:

DOOR				WINDOW			
NO.	WIDTH	HEIGHT	INTEL. HEIGHT	NO.	WIDTH	HEIGHT	INTEL. HEIGHT
D1	1000	2100	2100	W1	1200	1800	2100
D2	900	2100	2100	W2	1200	1200	2100
D3	750	2100	2100	W3	900	1200	2100
D4	1200	2100	2100	W4	750	1200	2100
D5	1000	2100	2100	W5	900	1000	2100
				W6	600	900	2100

REVISIONS

REV. NO.	REV. DATE	DESCRIPTION	REV. BY

AREA CALCULATION:-
 TYPE = BLOCK-1 (TOWER-3)
 GROUND FLOOR AREA = 583.740 SQ.M.
 FLAT AREA = 183.521 SQ.M.
 SERVICE AREA = 71.895 SQ.M.
 PARKING AREA = 328.324 SQ.M.
 TYPICAL FLOOR (1ST.-12TH.) AREA = @ 576.895 X12 = 6922.740 SQ.M.
 TOTAL BUILT UP AREA = 7506.48 SQ.M. (INCLUDING PARKING)
 LIFT MACHINE ROOM & STAIR HEAD ROOM, TOILET, UPS ROOM = 65.790 SQ.M.

Woodland Complex Private Limited
 Development Corporation Private Limited
 Director: [Signature] Director: [Signature]

SIGNATURE OF OWNER & SEAL
 WE DO HEREBY CERTIFY THAT THE FOUNDATION AND SUPERSTRUCTURE OF THE BUILDING PROPOSED FOR CONSTRUCTION ON PREMISES NO. MOUZA-BHASA, J.L. NO.-20, L.R. DAG. NO.- 483 TO 485, 489 TO 495, 497 TO 499, 513 TO 517, 727, P.S.- BISHNUPUR, DIST - 24 PGS (SOUTH) HAVE BEEN SO DESIGNED BY ME / US WILL MAKE SUCH FOUNDATION AND SUPERSTRUCTURE SAFE IN ALL RESPECTS INCLUDING THE CONSIDERATION OF BEARING CAPACITY AND SETTLEMENT OF SOIL ETC.

MALAY KUMAR GHOSH
 Regn. No. CA/92/14884
 35A, Dr. Sarat Banerjee Road, Kolkata-700029
MALAY KUMAR GHOSH
 REGN. NO. CA/92/14884
 35A, DR. SARAT BANERJEE ROAD, KOLKATA-700029
SIGNATURE OF ARCHITECT & SEAL

Koushik Sengupta
 B.E. (CIVIL), M.E. (STRUCTURE)
 ESE-1/76 (K.M.C.)
KOUSHIK SENGUPTA
 B.E. (CIVIL), M.E. (STRUCTURE)
 ESE - 1/76 (K. M. C.)
SIGNATURE OF STRUCTURAL ENGINEER & SEAL

ALOK ROY
 Engg. Regd. Geotechnical Engineer
 Kolkata Municipal Corporation
 Class A No.-G/74/11
 6A, Milan Park, Kolkata-700 084
ALOK ROY
 GTE - 1/11
 6A MILAN PARK, GARIA, KOLKATA- 700084.
SIGNATURE OF GEO-TECHNICAL ENGINEER & SEAL

TYPE BLOCK-2-TOWER-3
GROUND FLOOR PLAN, TYPICAL FLOOR (1ST. TO 12TH.) PLAN, FRONT ELEVATION.


DWG. NO. ESP / 2020/ EDEN JOKA / SANC / ARCHI-10

DESIGNED	M.G.	REF.
CHECKED	M.G.	SCALE 1:100
DEALT	SANDHYA	DATE 05.12.2020


ARCHITECT
 ESPACE PLANNING SERVICES PVT. LTD.
 35A Dr. SARAT BANERJEE ROAD, KOLKATA-700029
 FAX:PHONE-0314854130, 033-4654159, e-mail-espase@vsnl.co.in

- Noted and recommended for sanction the building plan No. C/3/74/1/KMDA/63(6/11)/height-39.335m. Subject to the condition
 - Before starting any construction, the site must conform with the plans Sanctioned and all the condition as proposed in the plan should be fulfilled.
 - All building materials necessary for construction should conform to standard specified in the N.B.C. of India.
 - Necessary steps should be taken for safety of lives of the adjoining public and private property during construction.
 - Construction site should be maintained to prevent mosquito breeding.
 - Design of all structural members including that of the foundation should conform to standard specified in the N.B.C. of India.
- The sanction is valid for 3 years from date of sanctioning
- Information required by the applicants to this end are :-
 - Commencement of work.
 - Completion of structural work up to plinth.
 - Completion of work.
 - No rain water pipe should be fixed or discharged on Road or Footpath.
 - The construction should be carried out as per specification of I.S. Code and sanctioned plan under the supervision of qualified empowered engineers.
 - Construction of garbage vat, soak pit & waste water should be done by the owners.
 - Any deviation of the sanctioned plan shall mean demolition.
- There should not be any court cases or any complaints from any corner in respect of the said property on per plan.
 - South 24 Parganas Zilla Parliament will not be held if any dispute arises at the site.


District Engineer
 South 24 Parganas



FRONT ELEVATION



TYPICAL FLOOR (1ST. TO 12TH.) PLAN



GROUND FLOOR PLAN

THIS DRAWING IS A PROPERTY OF ESPACE. 35A, DR. SARAT BANERJEE ROAD, KOLKATA-700029. ANY MODIFICATION, CHANGES, DEVIATIONS, REVISIONS IS NOT PERMISSIBLE WITHOUT PRIOR INTIMATION TO ESPACE. IN THE CONTRARY THIS WILL BE TREATED AS LEGAL ACT.