SCHEDULE OF FLOOR & ROOF BEAMS (CONC. GRADE -M30)

BEAM NOS.	BEAM SIZE	REINFORCEMENT					
		SUPPORT		SPAN		STIRRUPS	
		TOP	BOTTOM	TOP	BOTTOM	SUPPORT	SPAN
B1	230X450	4-16Ø	3-16Ø	3-16Ø	4-16Ø	8ℓ2ᴸ@100 CC	8ℓ2ᴸ@230 CC
B2	230X450	2-20Ø+4-16Ø	3-16Ø	3-16Ø	2-16Ø+4-16Ø	-DO-	-DO-
B3	230X450	2-16Ø	3-16Ø	3-16Ø	2-16Ø	-DO-	-DO-
B4A	230X450	6-16Ø	2-16Ø	6-16Ø	2-16Ø	-DO-	-DO-
B4	230X450	3-16Ø	3-16Ø	3-16Ø	4-16Ø	-DO-	-DO-
B5	230X600	4-16Ø	3-16Ø	3-16Ø	6-16Ø	-DO-	-DO-
B6	230X600	2-16Ø	2-16Ø	2-16Ø	3-16Ø	-DO-	-DO-
B7	230X600	2-16Ø	2-16Ø	2-16Ø	3-16Ø	-DO-	-DO-
B	230X600	6-16Ø	3-16Ø	——	——	-DO-	-DO-
T3	230X450	4-16Ø	2-16Ø	3-16Ø	4-16Ø	8ℓ2ᴸ@230 CC	
T3A	230X450	2-16Ø	2-16Ø	3-16Ø	4-16Ø	8ℓ2ᴸ@230 CC	

REINFORCEMENT

SCHEDULE OF PILE CAP

PILE CAP MARK	NO. OF PILES IN EACH GROUP	CASE NOS.	LENGTH	BREADTH	DEPTH	REINFORCEMENT DETAILS OF PILE CAP			
						BOTTOM REINFORCEMENT (ALONG BOTH WAYS)	TOP REINFORCEMENT (ALONG BOTH WAYS)		REINFORCEMENT DETAILS
PC1	2	1,2,3,4,A5,7,A,10,11,12, 13,14,15,16,17,18,A19, 20,21,22,23,24,25,26, 27,28,29,30,31,32,33, 34,35,A36,37,38,A39, A40,41,42,43,44,A45	2100	750	600	16-Ø-100 CC Both Ways	12-Ø-150 CC Both Ways	4-12	
PC2	3	8	2700/750	900	600	16-Ø-125 CC Both Ways		4-12	
PC3	4	LIFT + 21	3300	2700	1000	16-Ø-100 CC Both Ways	12-Ø-100 CC Both Ways	8-12	

SCHEDULE OF COLUMN

COLUMN MARK	REINFORCEMENT		
	GR. BET.PL.	2ND.BSMT.	4TH PL.
C1,A,B,C,D,E,F,G,H	8-Ø20 4-Ø16	8-Ø20 4-Ø16	8-Ø20 4-Ø16
C2	8-Ø20 4-Ø16	8-Ø20 4-Ø16	8-Ø20 4-Ø16
C3	8-Ø20 4-Ø16	8-Ø20 4-Ø16	8-Ø20 4-Ø16
C4	8-Ø20 4-Ø16	8-Ø20 4-Ø16	8-Ø20 4-Ø16
C5	8-Ø20 4-Ø16	8-Ø20 4-Ø16	8-Ø20 4-Ø16
C6	8-Ø20 4-Ø16	8-Ø20 4-Ø16	8-Ø20 4-Ø16

SCHEDULE OF SLAB *

SLAB MARK	TOP OR BOTTOM	ALONG SHORTER AXIS		ALONG LONGER AXIS	
		SHORT		SHORT	
		TOP	BOTTOM	TOP	BOTTOM
S1	TOP	8 mm Ø@mm c/c for length	8 mm Ø@mm c/c for length	8 mm Ø@mm c/c for length	8 mm Ø@mm c/c for length
	BOTTOM	8 mm Ø@mm c/c for length		8 mm Ø@mm c/c for length	
S2	TOP	8 mm Ø@mm c/c for length	8 mm Ø@mm c/c for length	8 mm Ø@mm c/c for length	8 mm Ø@mm c/c for length
	BOTTOM	8 mm Ø@mm c/c for length		8 mm Ø@mm c/c for length	
S3	TOP	8 mm Ø@mm c/c for length	8 mm Ø@mm c/c for length	8 mm Ø@mm c/c for length	8 mm Ø@mm c/c for length
	BOTTOM	8 mm Ø@mm c/c for length		8 mm Ø@mm c/c for length	

* SCHEDULE OF SLAB CASES *

THICKNESS OF WASH SLAB = 125 mm.
THICKNESS OF LANDING SLAB = 175 mm.
MAIN REINFORCEMENT = 12 mm Ø @ 150 mm c/c.
DISTRIBUTION BAR = 8 mm Ø @ 150 mm c/c.

SECTIONAL ELEVATION OF PC1-PC2

SCALE - 1:25

SECTIONAL ELEVATION OF PC3

SCALE - 1:25

DETAILS OF PC-1

SCALE - 1:25

DETAILS OF PC-2

SCALE - 1:25

DETAILS OF PC-3

SCALE - 1:25

SECTION 1-1

SCALE - 1:25

LONGITUDINAL SECTION OF 450 DIA PILE

SCALE - 1:25

SECTION OF SUMP UNDER GROUND WATER RESERVOIR

SECTION OF OVERHEAD WATER RESERVOIR

SCALE-1:25

SECTION OF LIFT WELL

SCALE-1:25

DETAILS OF PC-4

SCALE - 1:25

DETAILS OF LIFT

LIFT-450
SCALE - 1:25

STRUCTURAL LAY-OUT OF FOUNDATION

SCALE-1:125

STRUCTURAL LAY-OUT OF FOUNDATION

SCALE-1:125

ROAD DETAILS OF RAMP, PLAN

SCALE - 1:125

TYPICAL CURTAILMENT DETAIL OF SLAB REINFORCEMENT.

(FOR ONE WAY SLAB)

TYPICAL CURTAILMENT DETAIL OF FLOOR BEAM REINFORCEMENT.

(FOR ONE WAY SLAB)

SECTIONAL ELEVATION OF PC-1,PC-2

SECTIONAL ELEVATION OF PC-3

SCHEDULE OF STAIRCASE

STAIRCASE NO.	STAIRCASE TYPE	STEP SIZE	NO. OF STEPS	WAIST SLAB THICKNESS	LANDING SLAB THICKNESS	LANDING WIDTH	MAIN REINFORCEMENT	DISTRIBUTION REINFORCEMENT
S1	DOG LEGGED	150 mm RISE 300 mm TREAD	12	150 mm	150 mm	1200 mm	10 mm Ø @ 100 mm c/c	8 mm Ø @ 150 mm c/c

SCHEDULE OF STAIRCASE

SCHEDULE OF WALL

WALL MARK	LOCATION	THICKNESS	REINFORCEMENT	
			VERTICAL	HORIZONTAL
W1	ALL AROUND	230 mm	10 mm Ø @ 150 mm c/c	8 mm Ø @ 150 mm c/c

SCHEDULE OF SUMP

SUMP MARK	SIZE	REINFORCEMENT	
		BOTTOM	SIDE WALLS
SUMP	1250 X 1650 X 1000 DEEP	10 mm Ø @ 150 mm c/c	10 mm Ø @ 150 mm c/c

SCHEDULE OF LIFT

LIFT MARK	SIZE	REINFORCEMENT	
		BOTTOM	SIDE WALLS
LIFT	1250 X 1650 X 1000 DEEP	10 mm Ø @ 150 mm c/c	10 mm Ø @ 150 mm c/c

SCHEDULE OF OVERHEAD WATER RESERVOIR

RESERVOIR MARK	SIZE	REINFORCEMENT	
		BOTTOM	SIDE WALLS
OHR	3000 X 3000 X 1500 DEEP	10 mm Ø @ 150 mm c/c	10 mm Ø @ 150 mm c/c

SCHEDULE OF SUMP UNDER GROUND WATER RESERVOIR

SUMP MARK	SIZE	REINFORCEMENT	
		BOTTOM	SIDE WALLS
SUMP	3000 X 3000 X 1500 DEEP	10 mm Ø @ 150 mm c/c	10 mm Ø @ 150 mm c/c

DETAILS OF LIFT

LIFT-450
SCALE - 1:25

DETAILS OF OVERHEAD WATER RESERVOIR

SCALE-1:25

DETAILS OF SUMP UNDER GROUND WATER RESERVOIR

SCALE-1:25

LOADING : NO.1 : STRUCTURAL DRAWING.

USE
FOR SITE APPROVAL
NOT TO BE USED FOR CONSTRUCTION
DRAWING STATUS
DRAWN BY
CHECKED BY
APPROVED BY
DATE
DRG. REVIS.
DESCRIPTION
STRUCTURAL DRAWING FOR THE PROPOSED G+5 STOREY RAILING OF AARTI NUMA NOVA & DLF DUTTA TO BE CONSTRUCTED WITHIN MOUZA KHAVALI & JOLIS NEAR DAS NOSRE,MMD NOA UNDER BOMA NAGAR MUNICIPAL CORPORATION .

NOTES
SCHEDULE
SECTION
LAYOUT DRAWING
: ALL SEAL COLOUR.
: FOUNDATION PLAN.
: ALL TEXT.
: FOUNDATION PLAN.
: ALL BEAM.

SIGN OF OWNER

MAKE & SIGNATURE NO. OF ARCHITECT

CERTIFICATE OF THE CIVIL ENGINEER.

CERTIFY THAT THE STRUCTURAL DRAWING AND DESIGN OF BOTH THE FOUNDATION AND SUPERSTRUCTURE OF THE BUILDING HAS BEEN MADE UNDER MY SUPERVISION AND CONFORMS TO THE BUILDING BYE LAWS AND REGULATIONS PRESCRIBED BY THE MUNICIPAL AUTHORITY AND CONFORMS TO THE STRUCTURAL DESIGN AND DRAWINGS AS PER THE BUILDING BYE LAWS AND REGULATIONS PRESCRIBED BY THE MUNICIPAL AUTHORITY AND CONFORMS TO THE MATERIAL SPECIFICATION