





PROPOSED (G+4) FIVE STORIED RESIDENTIAL CUM COMMERCIAL BUILDING PLAN AT HOLDING NO:-47, NETAJI PALLY , IN WARD NO:- 22 UNDER R.S. DAG NO.-1822(P) L.R. DAG NO. 1373(P) L.S. KHATIAN NO:- 1281, L.R.KHATIAN NO:- 1564, MOUZA & MUNICIPALITY:-SOUTH DUMDUM MUNICIPALITY, P.S.-BIDHANNAGAR (PRT), HOOGHLY

NAME OF OWNER :SRI TAPAS GHOSH

SPECIFICATIONS OF CONSTRUCTION :-

1. 1ST CLASS BRICK (F.G) IN SUPER STRUCTER
2. 75 THICK 1ST CLASS BRICK WORK BY (1: 4) CEMENT SAND MORTER WITH H.B. WIRE BEETING
3. LEAN CONC. (1:3:6) WITH 18 mm DOWN GRADED STONE CHIPS WITH OUT REAR.
4. R.C.C. (M-20) MIX. 50% FOR ROOF SLAB BEAM COLUMN AND LINTEL FOUNDATION.
5. CEMENTS AND PLASTER 20 m.m. THK. ON OUTSIDE WALL AND 12 m.m. THK. ON INSIDE WALL
6. 10m.m. THK PLASTER ON CEILING R.C.C. CHALLA.
6. 25 m.m. THK. I.P.S. FLOORING WITH NEAT CEMENT AT 1:2 IN INCLUDING SKIRTING
7. WOOD WORK :- SAL WOOD SHALL BE USED FOR DOORS AND WINDOWS FRAME
8. TORQUE STEEL BARS FOR COLUMN ,BEAM ,LINTEL SLAB AND FOUNDATION INCLUDING DISTRIBUTORS AND BINDERS. (FE-415)
9. ALL OUTSIDE WALL 250 THK. AND INSIDE WALL 125 & 75 THK.
10. MATERIALS TO BE USED :-STONE CHIPS- 19m.m. DOWN GRADED.
11. SAND:- MEDIUM COARSE, CREAMY, ORDINARY PORTLAND.
12. COVER TO MAIN REINFOR CEMENT :-BEAM -25M M , COL.- 40M M , F/TH.- 50M M SLAB - 15M M

AREA STATEMENT

TOTAL AREA OF LAND :- 3K-48CH (1) 0FTCH 261.67 SQM

GROUND FL. AREA	130.57 SQM/1405 SFT
FIRST FLOOR AREA	130.57 SQM/1405 SFT
SECOND FL. AREA	130.57 SQM/1405 SFT
THIRD FLOOR AREA	130.57 SQM/1405 SFT
FOURTH FLOOR AREA	130.57 SQM/1405 SFT
TOTAL BUILD UP AREA	652.85 SQM/7025 SFT

SCHEDULE OF DOOR & WINDOW

DOOR MKD	DOOR BREADTH	DOOR HEIGHT	WINDOW MKD	WINDOW BREADTH	WINDOW HEIGHT
D	1050	2100	W	1500	1200
D1	900	2000	W1	1200	1200
D2	750	2000	W2	600	1200
R.S.D	1500	2100			

SIG. OF OWNER:-

RUMPA BHATTACHARYA
(Diploma in Civil Engineering)
Bangasree Pally-1, Angus,
Hooghly, Pin-712221
Licence No.- Civil-12...

SIGNATURE OF L.B.S

SIGNATURE OF S.A.E /A.E