

**SCHEDULE OF COLUMNS:**  
(GRADE OF CONCRETE : M25 & GRADE OF STEEL : Fe500)

ROOF TO FOUNDATION	M-25		
	300	300	300
COL. SIZE	(300 X 600)	(300 X 500)	(300 X 450)
COL. MKD.	C21, C30	C11, C33	REST COLUMNS
LINK	8T @ 75 / 150 C/C	8T @ 75 / 150 C/C	8T @ 75 / 150 C/C

**SCHEDULE OF FLOOR BEAM:**  
(GRADE OF CONCRETE : M25 & GRADE OF STEEL : Fe500)

BEAM MKD.	BEAM SIZE	MAIN REINFORCEMENT				STIRRUPS	
		SUPPORT		SPAN		SUPPORT	SPAN
		TOP	BOT.	TOP	BOT.		
B-1	250X400	3-16 <sup>+</sup> 2-12 <sup>+</sup>	3-16 <sup>+</sup>	2-16 <sup>+</sup>	3-16 <sup>+</sup>	8 <sup>+</sup> -2L @ 100 C/C	8 <sup>+</sup> -2L @ 150 C/C
B-1A	250X400	3-16 <sup>+</sup> 2-12 <sup>+</sup>	3-16 <sup>+</sup>	3-16 <sup>+</sup> 2-12 <sup>+</sup>	3-16 <sup>+</sup>	8 <sup>+</sup> -2L @ 100 C/C	8 <sup>+</sup> -2L @ 100 C/C
B-2	250X400	3-16 <sup>+</sup> 2-12 <sup>+</sup>	3-16 <sup>+</sup>	2-16 <sup>+</sup>	3-16 <sup>+</sup> 2-12 <sup>+</sup>	8 <sup>+</sup> -2L @ 100 C/C	8 <sup>+</sup> -2L @ 100 C/C
B-3	250X400	3-16 <sup>+</sup>	3-16 <sup>+</sup>	2-16 <sup>+</sup>	3-16 <sup>+</sup>	8 <sup>+</sup> -2L @ 100 C/C	8 <sup>+</sup> -2L @ 150 C/C
B-4	250X400	3-16 <sup>+</sup>	2-16 <sup>+</sup>	2-16 <sup>+</sup>	3-16 <sup>+</sup>	8 <sup>+</sup> -2L @ 100 C/C	8 <sup>+</sup> -2L @ 100 C/C
B-5	250X400	3-16 <sup>+</sup> 2-12 <sup>+</sup>	2-16 <sup>+</sup>	2-16 <sup>+</sup>	3-16 <sup>+</sup> 2-12 <sup>+</sup>	8 <sup>+</sup> -2L @ 100 C/C	8 <sup>+</sup> -2L @ 100 C/C
B-6	250X400	2-16 <sup>+</sup>	2-16 <sup>+</sup>	2-16 <sup>+</sup>	2-16 <sup>+</sup>	8 <sup>+</sup> -2L @ 100 C/C	8 <sup>+</sup> -2L @ 150 C/C
HLB	250X400	3-16 <sup>+</sup> 2-12 <sup>+</sup>	2-16 <sup>+</sup>	2-16 <sup>+</sup>	3-16 <sup>+</sup> 2-12 <sup>+</sup>	8 <sup>+</sup> -2L @ 100 C/C	8 <sup>+</sup> -2L @ 100 C/C


**SCHEDULE OF PLINTH BEAM:**  
(GRADE OF CONCRETE : M25 & GRADE OF STEEL : Fe500)

BEAM MKD.	BEAM SIZE	MAIN REINFORCEMENT				STIRRUPS	
		SUPPORT		SPAN		SUPPORT	SPAN
		TOP	BOT.	TOP	BOT.		
PB-1	250X400	3-16 <sup>+</sup>	3-16 <sup>+</sup>	3-16 <sup>+</sup>	3-16 <sup>+</sup>	8 <sup>+</sup> -2L @ 100 C/C	8 <sup>+</sup> -2L @ 150 C/C
PB-2	250X400	3-16 <sup>+</sup>	3-16 <sup>+</sup>	3-16 <sup>+</sup>	3-16 <sup>+</sup>	8 <sup>+</sup> -2L @ 100 C/C	8 <sup>+</sup> -2L @ 100 C/C
PB-3	250X400	3-12 <sup>+</sup>	3-12 <sup>+</sup>	3-12 <sup>+</sup>	3-12 <sup>+</sup>	8 <sup>+</sup> -2L @ 100 C/C	8 <sup>+</sup> -2L @ 150 C/C
PB-4	250X400	2-16 <sup>+</sup>	3-16 <sup>+</sup>	2-16 <sup>+</sup>	3-16 <sup>+</sup>	8 <sup>+</sup> -2L @ 100 C/C	8 <sup>+</sup> -2L @ 150 C/C



**SCHEDULE OF FLOOR SLAB:**  
(GRADE OF CONCRETE : M25 & GRADE OF STEEL : Fe500)

SLAB MKD.	SLAB THICKNESS (MM)	REINFORCEMENT			
		SHORTER SPAN		LONGER SPAN	
		SUPPORT (TOP)	SPAN (BOTTOM)	SUPPORT (TOP)	SPAN (BOTTOM)
S1	125	8 <sup>+</sup> @ 125 C/C	8 <sup>+</sup> @ 150 C/C	8 <sup>+</sup> @ 150 C/C	8 <sup>+</sup> @ 175 C/C
S2	125	8 <sup>+</sup> @ 175 C/C	8 <sup>+</sup> @ 200 C/C	8 <sup>+</sup> @ 175 C/C	8 <sup>+</sup> @ 200 C/C


PROVIDE 8<sup>+</sup>@ 200 C/C DISTRIBUTOR BAR WHERE EVER REQUIRED




G.A. OF TYPICAL FLOOR BEAM SLAB LAYOUT PLAN (BLOCK -B)  
SCALE-1:100




TYP. R.C.C. DET. OF STAIR FLIGHT.  
SCALE 1:25



G.A. OF COLUMN LAYOUT PLAN (BLOCK-B)  
SCALE-1:100



G.A. OF PLINTH BEAM LAYOUT PLAN (BLOCK-B)  
SCALE-1:100



COLUMN AND JOINT DETAILING  
SPL. NOTES:-  
1. THE LENGTH OF SPL. SHALL NOT BE LESS THAN EITHER OF THE FOLLOWING (a) LARGER LATERAL DIMENSION OF THE MEMBER AT THE SECTION. (b) 1/3 OF CLEAR SPAN OF THE MEMBER. AND (c) 450 mm.

- NOTES:-**
- ALL DIMENSIONS ARE IN MM. UNLESS OTHERWISE MENTIONED.
  - SUPER STRUCTURE : SUPER STRUCTURE SHALL BE OF LIGHT WEIGHT A.A.C BLOCK IN 1:6 CEMENT MORTAR.
  - GRADE OF CONC. M-25, OTHERWISE MENTIONED
  - ALL MATERIALS SHALL CONFORM TO RELEVANT I.S CODES.
  - FOR STEEL GRADE Fe 500 AS PER I.S 1786-2008.
  - LAPS, SPLICES & BOND LENGTH SHOULD BE 50 D WHERE 'D' IS THE SMALLEST BAR DIA.
  - ALL DISTRIBUTION BARS ARE 8 TOR @ 200 C/C AND TO BE PROVIDED WHEREVER REQUIRED
  - ALL SPACER BARS ARE 25 TOR @ 1000 C/C AND TO BE PROVIDED WHEREVER REQUIRED
  - MINIMUM CLEAR COVER TO MAIN REINFORCEMENT IS AS FOLLOWS:

MEMBER	TOP	BOTTOM	SIDE
a. BEAM	25	25	25
b. COLUMN	—	—	40
c. SLAB	20	20	20
d. PILECAP	60	75	60

SPACE FOR OFFICE USE:

May be Technically vetted  
Assistant Engineer  
Hooghly Zilla Parishad

Technically vetted  
District Engineer  
Hooghly Zilla Parishad

THIS IS TO CERTIFY THAT I SHALL NOT ON A LATER DATE, MAKE ANY ADDITION OR ALTERATION TO THIS PLAN. THIS IS CERTIFIED THAT I HAVE GONE THROUGH THE NBC OF INDIA AND ALSO ABIDE BY THOSE RULES DURING AND LATER CONSTRUCTION OF BUILDING.

*S. Paridal*  
SIGNATURE OF THE OWNER

*Tanmoy Das*  
TANMOY DAS  
B.Tech (Civil), M.Tech (Struct. Engg.) (Pursuing)  
AMIE, MIGS, Chartered Engineer  
Empanelled L.B.S. (Class-I)  
Kolkata Municipal Corporation  
License No.- LBS/1/1980  
SIGNATURE OF ARCHITECT/L.B.S

THE STRUCTURAL DESIGN AND DRAWING OF BOTH FOUNDATION AND SUPERSTRUCTURE OF THE BUILDING HAS BEEN MADE BY ME, CONSIDERING ALL POSSIBLE LOADS INCLUDING THE SEISMIC LOAD AS PER THE NATIONAL BUILDING CODE OF INDIA AND CERTIFIED THAT IT IS SAFE AND STABLE IN ALL RESPECT IF IT IS CONSTRUCTED AS PER THIS DRAWING.

*Tanmoy Das*  
TANMOY DAS  
B.Tech (Civil), M.Tech (Struct. Engg.) (Pursuing)  
AMIE, MIGS, Chartered Engineer  
Empanelled Structural Engineer  
Kolkata Municipal Corporation  
License No.- ESE/1/291  
SIGNATURE OF STRUCTURAL ENGINEER.

SIGNATURE OF STRUCTURAL ENGINEER.

VETTED BY:

Checked & Vetted  
Dr. Partha Ghosh  
B. E. (Civil), M.E. (Structural Engg.), Ph. D. (Engg.)  
Professor  
Construction Engg. Department  
Jadavpur University, Kolkata - 700 103

**PROJECT :**  
PROPOSED G+4 STORED BUILDING "MADHUBAN LAKE VIEW" AT NAITTY ROAD, CHAKRABORTY NAGAR UNDER KANAIPUR GRAM PANCHAYAT, MOUZA- BARABHERA, J.L.NO.- 5, P.S.- UTTARPARA, DIST.-HOOGHLY, W.B. OF R. S. DAG NO.-1221(P), R. S. KHATIAN NO.-901(640), L. R. DAG NO.-1475, L. R. KHATIAN NO.- 7804.

**TITLE:**  
G.A & R.C.C DETAIL OF STRUCTURE  
**DRAWN BY:-** S.B **DATE:-** 23.05.2024 **SHEET NO. -** 03/03  
**CHECKED BY:-** TANMOY DAS **SCALE:-** 1:100, 20, 25 **REVISION -** 00  
**JOB NO. -**  
**DRG. NO. -** ARCHSTRUCT/STR/VET/04/05/2024  
**STATUS**  INFORMATION  APPROVAL  SUBMISSION