SCHEDULE OF COLUMN :- (BLOCK-1E) (M20 AND FE 500)

COLUMN NOS.	SIZE (MMxMM)	FOUNDATION TO 2ND. FL.	2ND.FL. TO 4TH. FL.	4TH. FL. TO ROOF ABOVE
EC1	250X450	4-16#+6-12#	4-16#+4-12#	8-12#
EC2	250X450	8-16#	8-16#+2-12#	4-16#+4-12#
EC3	250X450	6-16#+2-12#	6-16#+2-12#	4-16#+4-12#
EC4	250X450	8-16#	8-16#	6-16#+2-12#
EC5	250X450	8-16#	8-16#	6-16#+2-12#
EC6	250X450	6-16#+2-12#	6-16#+2-12#	4-16#+4-12#
EC7	250X450	6-16#+2-12#	6-16#+2-12#	4-16#+4-12#
EC8	250X450	4-20#+4-16#	4-20#+4-16#	8-16#
EC9	250X500	4-20#+6-16#	10-16#	10-16#
EC10	250X450	8-16#	6-16#+2-12#	4-16#+4-12#
EC11	250X450	4-20#+4-16#	4-20#+4-16#	8-16#
EC12	250X450	8-20#	4-20#+4-16#	8-16#
EC13	250X1125	12-16#+6-12#	12-16#+6-12#	12-16#+6-12#
EC14	250X450	8-20#	4-20#+4-16#	8-16#
EC15	250X450	4-20#+4-16#	4-20#+4-16#	8-16#
EC16	250X500	6-20#+2-16#	4-20#+6-16#	10-16#
EC17	250X450	8-16#	6-16#+2-12#	6-16#+2-12#
EC18	250X500	10-16#	8-16#+2-12#	8-16#+2-12#
EC19	250X500	4-20#+4-16#	8-16#	8-16#
EC20	250X450	8-16#	8-16#	6-16#+2-12#
EC21	250X450	4-20#+4-16#	4-20#+4-16#	8-16#
EC22	250X450	8-20#	4-20#+4-16#	8-16#
EC23	250X500	10-20#	4-20#+6-16#	10-16#
EC24	250X500	10-20#	4-20#+6-16#	10-16#
EC25	250X450	4-20#+4-16#	4-20#+4-16#	8-16#
EC26	250X500	6-20#+2-16#	4-20#+6-16#	10-16#
EC27	250X500	8-20#+2-16#	4-20#+6-16#	10-16#
EC28	250X450	4-20#+4-16#	8-16#	8-16#
EC29	250X450	8-16#	6-16#+2-12#	4-16#+4-12#
EC30	250X500	8-16#	6-16#+2-12#	6-16#+2-12#
EC31	250X600	4-20#+6-16#	10-16#	10-16#
EC32	250X450	8-20#	4-20#+4-16#	8-16#
EC33	250X450	8-20#	4-20#+4-16#	8-16#
EC34	250X450	6-16#+2-12#	4-16#+4-12#	4-16#+4-12#
EC35	250X450	4-20#+4-16#	4-20#+4-16#	8-16#
EC36	250X450	4-20#+4-16#	4-20#+4-16#	8-16#
EC37	OMITTED			
EC38	250X500	10-16#	10-16#	10-16#
EC39	250X450	4-20#+4-16#	4-20#+4-16#	8-16#
EC40	250X500	4-20#+4-16#	10-16#	10-16#
EC41	250X500	10-16#	10-16#	8-16#+2-12#
EC42	250X500	10-16#	10-16#	8-16#+2-12#
EC43	300X450	10-16#	10-16#	8-16#+2-12#
EC44	250X300	6-16#+2-12#	6-16#+2-12#	4-16#+4-12#
EC45	250X500	8-16#+2-12#	8-16#+2-12#	4-16#+4-12#
EC46	250X500	10-16#	8-16#+2-12#	4-16#+4-12#
EC47	250X500	10-16#	8-16#+2-12#	4-16#+4-12#

SCHEDULE OF FLOOR BEAM (M20 AND FE 500) BLOCK-1

BEAM MK'D.	SIZE (MMxMM)	TOP ALTH	TOP EXT(AT SUPT.)	BOTT. ALTH	BOTT. EXT(MID SPAN)	STIRRUPS (2 LEGGED) AT SUPPORT	STIRRUPS (2 LEGGED) AT SPAN
B1	250x450	3-16#	1-12#, 2-20+1-16#(Cont'l Ext)	3-16#	2-12#	8@100mmC/C	8@150mmC/C
B1A	250x450	3-16#+2-20#	-	2-16#+2-12#	-	8@100mmC/C	8@150mmC/C
B2	250x450	3-16#	1-16#, 2-20+1-16#(Cont'l Ext)	2-16#	2-16#	8@100mmC/C	8@150mmC/C
B2A	250x450	3-16#+2-20#	-	4-16#	-	8@100mmC/C	8@150mmC/C
B3	250x450	3-16#	2-16#	3-16#	2-16#	8@100mmC/C	8@150mmC/C
B3A	250x450	3-16#	-	3-16#	-	8@100mmC/C	8@150mmC/C
B4	250x450	2-16#	2-12#	3-16#	-	8@100mmC/C	8@150mmC/C
B5	250x450	3-16#	2-16#	4-16#	-	8@100mmC/C	8@150mmC/C
B6	250x450	2-16#	1-16#	4-16#	-	8@100mmC/C	8@150mmC/C
B7	250x450	2-16#	2-16#	2-20#	2-16#	8@100mmC/C	8@150mmC/C
B8	250x450	3-16#	-	3-16#	-	8@100mmC/C	8@150mmC/C
B9	250x450	2-16#+1-12 #2	2-16#	3-16#	2-20#	8@100mmC/C	8@150mmC/C
B10	250x450	2-16#	2-20#	3-16#	2-20#	8@100mmC/C	8@150mmC/C
B11	250x450	2-16#	2-20#	2-20#	2-16#	8@100mmC/C	8@150mmC/C

SCHEDULE OF SLAB (S1)

SLAB THICKNESS AS MENTIONED :- 115 MM (M20 AND FE 500)
(ALONG SHORTER DIRECTION)

SUPPORT	8mm@ 150mm c/c at top of support & extended upto L/3 from beam.
SPAN	8mm@ 150mm c/c at span & alternately curtailed at L/4 from beam

SLAB THICKNESS AS MENTIONED :-115 MM (M20 AND FE 500)
(ALONG LONGER DIRECTION)

SUPPORT	8mm@ 165mm c/c at top of support & extended upto L/3 from beam.
SPAN	8mm@ 175mm c/c at span & alternately curtailed at L/4 from beam

SCHEDULE OF SLAB (S2)

SLAB THICKNESS AS MENTIONED :- 125 MM (M20 AND FE 500)
(ALONG SHORTER DIRECTION)

SUPPORT	8mm@ 125mm c/c at top of support & extended upto L/3 from beam.
SPAN	8mm@ 150mm c/c at span & alternately curtailed at L/4 from beam

SLAB THICKNESS AS MENTIONED :-125 MM (M20 AND FE 500)
(ALONG LONGER DIRECTION)

SUPPORT	8mm@ 165mm c/c at top of support & extended upto L/3 from beam.
SPAN	8mm@ 175mm c/c at span & alternately curtailed at L/4 from beam

SCHEDULE OF SLAB (S2)

SLAB THICKNESS AS MENTIONED :- 135 MM (M20 AND FE 500)
(ALONG SHORTER DIRECTION)

SUPPORT	8mm@ 125mm c/c at top of support & extended upto L/3 from beam.
SPAN	8mm@ 150mm c/c at span & alternately curtailed at L/4 from beam

SLAB THICKNESS AS MENTIONED :-135 MM (M20 AND FE 500)
(ALONG LONGER DIRECTION)

SUPPORT	8mm@ 165mm c/c at top of support & extended upto L/3 from beam.
SPAN	8mm@ 175mm c/c at span & alternately curtailed at L/4 from beam

SCHEDULE OF TIE BEAM (M20 AND FE 500)

MK'D.	SIZE (MMxMM)	TOP ALTH	TOP EXT(AT SUPT.)	BOTT. ALTH	BOTT. EXTEND SPAN	STIRRUPS (2 LEGGED) AT SUPPORT	STIRRUPS (2 LEGGED) AT SPAN
TB1	250x450	2-12#T	2-16#T	2-16#T	2-12#T	8@100mm C/C	8@150mm C/C
TB2	250x450	2-12#T	-	3-16#T	-	8@100mm C/C	8@150mm C/C
TB3	250x450	3-16#T	2-16#T	2-16#T	2-16#T	8@100mm C/C	8@150mm C/C
TB4	250x450	2-16#T	2-12#T	2-16#T	2-12#T	8@100mm C/C	8@150mm C/C
TB5	250x450	2-16#T	-	2-16#T	-	8@100mm C/C	8@150mm C/C



TYPICAL FLOOR BEAM LAYOUT PLAN (BLOCK-1E)
SCALE-1:100



COLUMN LAYOUT PLAN (BLOCK-1E)
SCALE-1:100



TIE BEAM LAYOUT PLAN (BLOCK-1E)
SCALE-1:100



LONG SECTION OF COL. SHOWING LINK DETAILS



TYPICAL DETAIL OF BEAM COLUMN JUNCTION



TYP. DETAIL OF FOUNDATION
SCALE 1:25



R.C. DETAILS OF LIFT WALL BELOW PINTH LEV.



R.C. DETAILS OF LIFT WALL TYPICAL FLOOR PINTH LEV.



TYP.DET.OF FIRST FLIGHT SECTION

TYP.DET.OF SECOND FLIGHT SECTION

NOTES :-

1. ALL DIMENSIONS ARE IN MM
2. ALL CONCRETE SHOULD BE OF GRADE M20 UNLESS SPECIFIED
3. COVER TO REINFORCEMENT.
   COLUMN = 40mm , BEAM = 30mm
   SLAB = 15mm , FOUNDATION = 50mm
4. DEPTH OF EXCAVATION OF UNDER GROUND SUMP SHOULD BE ABOVE THAT OF FOUNDATION.
5. DO NOT SCALE THE DRAWING , FOLLOW WITH DIMENSION.
6. ALL WALLS ARE AS PER ARCHITECTURAL DRAWINGS.
7. LEAN CONCRETE (1:3:6) NOMINAL MIX 75 THK. SHALL BE PROVIDED UNDER FOUNDATION.
8. THE DRAWINGS SHOULD BE STUDIED CAREFULLY AND ALL DIMENSIONS SHOWN HERE SHOULD BE CHECKED AT SITE. CLARIFICATION REGARDING DISCREPANCY IF ANY, SHOULD BE OBTAINED BEFORE COMMENCEMENT OF WORK.
9. SPACER BAR USED SHALL BE OF 20mm. OR DIAMETER OF THE BAR USED IN THE JOB WHICH IS LARGER.
10. STEEL TO BE USE SHOULD BE OF Fe-500 GRADE. REINFORCEMENT SHOULD BE WITH COLD TWISTED DEFORMED BARS CONFIRMING TO IS : - 1786 AND HAVE BEEN SHOWN AS ε
11. DEPTH OF EXCAVATION OF UNDER GROUND SUMP/RESERVOIR SHOULD BE ABOVE THE DEPTH OF FOUNDATION OF THE ADJACENT BUILDING / STRUCTURE.
12. LAP LENGTH OF STEEL BAR SHALL BE 50dia OF BAR

Consillium Attorney
REALMARK REALTY PVT. LTD.
Authorised Signatory/Director

SIGNATURE OF OWNER

CERTIFICATE OF STRUCTURAL ENGINEER

CERTIFIED THAT, "THE STRUCTURAL DESIGN & DRAWINGS OF BOTH FOUNDATION & SUPER STRUCTURE OF THE BUILDING HAS BEEN MADE BY ME CONSIDERING ALL POSSIBLE LOADS INCLUDING THE SEISMIC LOAD AS PER THE NATIONAL BUILDING CODE OF INDIA & CERTIFIED THAT IT IS SAFE & STABLE IN ALL RESPECTS".

SUBIR CHANDRA SANYAL
B. C.E., A. M. I., STRUCT. E. (I)
E. S. E. NO. 840, CLASS-I
E. S. E. NO. 857, CLASS-I
RAJPUR-SONARPUR MUNICIPALITY

SIGNATURE OF STRUCTURAL ENGINEER.

CERTIFICATE OF ARCHITECT

THE E.B.S. HAS CERTIFIED ON THE PLAN ITSELF WITH FULL RESPONSIBILITY THAT THE BUILDING PLAN HAS BEEN DRAWN UP AS PER PROVISION OF WEST BENGAL MUNICIPAL BUILDING RULES 2007, AS AMENDED FROM TIME TO TIME AND THAT THE SITE CONDITION INCLUDING THE WIDTH OF THE ABUTTING ROAD CONFIRM WITH THE PLAN AND IT IS A 'BUILD ABLE SITE AND NOT A TANK OR A FILLED UP TANK.

RAJKUMAR AGARWAL (E.B.A.)
RAJPUR SONARPUR MUNICIPALITY
NO. AS/1/R.JP/SONARPUR

SIGNATURE OF ARCHITECT

RUPAK KUMAR BANERJEE
B.SC., M.E., MIGS
M.I.E., CHARTERED ENGINEER
ENL/1701/3(e) TECHNICAL ENGINEER (A.M.C.)
G.T.I/93(K.M.C), LM-1279
M-183678-5
GTER-H1DCO/09/0014
01/RUP SONYO.TCP/14-15

SIGNATURE OF GEO-TECHNICAL ENGINEER

TITLE

COLUMN & TIE-BEAM LAYOUT PLAN WITH DETAILS. (BLOCK-1E)

PROJECT

STRUCTURAL DRAWING FOR A PROPOSED G+IV (15.45 MT. HT.) STORIEDRESIDENTIAL BUILDING AT HOLDING NO.-484, GHOSHAL PARA, WARD NO-23, R.S & L.R DAG NO -213, 353, 354 & 355, R.S KHATIAN NO. - 82 & 387, LR KHATIAN NO. 1619 , 1620 , 1621, 1622, 1623, 1624, 1625, 1626 1627, 1628, 1629, 1630, JL NO. 77, MOUZA.- MANIKPORE, P.S- SONARPUR, SOUTH 24 PARAGNAS UNDER RAJPUR - SONARPUR MUNICIPALITY.

DATE	JOB. NO.	DEALT	CHECKED	SHEET NO.
30.09.19	STRUC/484	SOMNATH	DIPANKAR	2 OF 7

SCALE (1:150, 100, 50, 40/0, 4000)

ARCHITECT

RAJ AGRAWAL & ASSOCIATES
8B, ROYD STREET, KOLKATA - 16

Sanyalson Associates Consultant Pvt. Ltd.
CONSULTANT PLANNER & STRUCTURAL ENGINEERS
P-157 KANUNGO PARK. KOLKATA-84

FOR OFFICE USE ONLY

Structural plan as submitted by the structural Engineer have been kept with Building Plan No. 21/09/23/45 Dated On.....
for record of the Rajpur-Sonarpur Municipality without hereof taken any deviation from the submitted structural plan at site in regard to the time of erection without submitting fresh structural plan along with Architectural and capacity certificate as prescribed fresh necessary check should be taken for the safety of the adjoining premises public private place etc and safety of human life during Construction

Sig. of Assistant Engineer
Technical P.M.D.
RAJPUR-SONARPUR MUNICIPALITY