

Plan for Water Supply arrangement including SEMILI G. & O. H. reservoirs should be submitted at the Office of the Ex-Engineer Water Supply and the sanction obtained before proceeding with the work of Water Supply any deviation may lead to disconnection/demolition.

CONSTRUCTION SITE SHALL BE MAINTAINED TO PREVENT MOSQUITO BREEDING AS REQUIRED U/S 496 (1) & (2) OF CMC ACT 1980. IN SUCH MANNER SO THAT ALL WATER COLLECTION & PARTICULARLY LIFT WELLS, VATS, BASEMENT CURING SITES, OPEN RECEPTACLES ETC. MUST BE EMPITED COMPLETELY TWICE A WEEK.

Sanctioned By: Assistant Engineer (C-B) Br. No..........

Approved By: MB(MB, NO: 549 has don No: 103/18-19. The Building Committee 27/7/20/8

Before starting any Construction the site must conform with the plans sanctioned and all theconditions as proposed in the plan should be fulfilled. The validity of the written permission to execute the work is subject to the above conditions.

The sanction refers to the proposed portion shown in red and the Executive Engineers makes no admission as to the correctness of the plan.

Design of all Structural Members including that of the foundation should conform to Standards specified in the National Building Code of India

All Building Materials to necessary & construction should conform's to standered specified in the National Building Code of India. Necessary steps should be taken

for the safety of the lives of the adjoining public and private

properties during construction. Non Commencement of Erection/ Re-Erection within Five year will Require Fresh Application for Sanction

DEVIATION WOULD MEAN DEMOLITION

and the second of the second o

APPROVED

A suitable pump has to be provided i.e. pumping unfiltered water for the distribution to the flushing cisterns and urinals in the building incase unfiltered water from street

main is not available.

cost and risk of the owner.

The building materials that will be stacked on Road/Passage or Foot-path beyond 3-months or after construction of G. Floor, whichever is earlier may be seized forthwith by the K.M.C. at the

THE KOLKATA MUNICIPAL CORPORA > Date 17/12/19 Borough No..... Ex Engineer / Asst Engineer Br. No.... 2... Bor No....... \* BUILDING DEPARTMENT \*

THE SANCTION IS VALIED

UP TO....16/12/2024...

Sanctioned subject to demolition of existing structure to provide open space as per plan before construction is started Executive Engineer (C)

Asst. Engineer (C) Br. PLAN BR. 🕺 No rain water pipe should be fixed or

discharged on Road or Footpath. Drainage plan should be submitted at the Borough Executive Engineer's Office and the sanction obtained before proceeding with the drainage work.

Any unathorised construction done in deviation from the Sanction Building permit and the Completion Plans after issuance of this Completion Plans may cause revocation of the Occupancy Certificate.

Sanctioned conditionally on an undertaking duly registered from the owner's to the effect till they will not evict any tenants & will also provide the tenants with identical area in and around the premises by mutual arrangements.

120 Par-2/17-18

A. Preventive measures need to be taken for pollution free environment: a) Wrap construction area/buildings with geotextile fabric installing dust barriers, or other actions, as

appropriate for the location, Apply water and maintain soils in a visible damp or crusted condition for temporary stabilization.

c) Apply water prior to leveling or any other earth moving activity to keep the soil moist throughout the d) Limit whicle speeds to 15 mpls on the work site.

e) Clean wheels and undercarriage of haul trucks prior to leaving construction site. f) Apply and maintain dust suppressant on haul routes. g) Apply a cover or screen to stockplies and stabilize stockplies at completion of activity by water and maintain a dust polliative to all outer surfaces of the stockplies; h) Stabilize surface soils where loaders, support equipment and vehicles will operate by using water and maintain surface soils in a stabilized condition where loaders, support equipment and vehicles will operate;

1) Stabilize adjacent disturbed soils following paving activities with immediate landscaping activity or installation of vegetative or rock cover.

i) Maintain de control during working hours and clean track out from paved surfaces at the end of the work side. Track out must now extend 50 feet or more and must be cleaned daily, at the k) Stabilize sloping surfaces using soft binders until vegetation or ground cover can effectively stabilize. the slope,

1) Disposal of debris in consultation with the local authorities following proper environmental management practice. m) During construction work, including sutting of marbles, ambient noise level should not exceed more than 65 dB(A).

B. Practicus to be discarded for pollution free Environment:- .

a) Don't dispose of debris indiscriminately,

Don's allow the vehicles to run at high speed within the work site. c) Don't cut materials without proper dust control/noise control facility. d) Don't keep materials without effective cover. a) Don't allow access in the work area except workers to limit soil disturbance and prevent access by

fencing, ditches, vegetation, berms or other suitable barrier.

f) Don't leave the soll, sand and cement stack uncovered. g) Don't keep materials or debris on the roads or pavements. h) Burning of old tyres in hot mix plant as a fuel during construction and repair of the roads for melting coal tar should be discarded:

> 0110001110 Executive angineer, Br.-X The Kolkato Municipal Carpa. Building Department, Br.-X Dated 17/12/19 Dy