

PARTY'S COPY

Plan for Water Supply arrangement including SEMILI G. & O. H. reservoirs should be submitted at the Office of the Ex-Engineer Water Supply and the sanction obtained before proceeding with the work of Water Supply any deviation may lead to disconnection/demolition.

CONSTRUCTION SITE SHALL BE MAINTAINED TO PREVENT MOSQUITO BREEDING AS REQUIRED U/S 496 (1) & (2) OF CMC ACT 1980. IN SUCH MANNER SO THAT ALL WATER COLLECTION & PARTICULARLY LIFT WELLS, VATS, BASEMENT CURING SITES, OPEN RECEPTACLES ETC. MUST BE EMPITED COMPLETELY

Sanctioned By: Assistant Engineer (C-B) Br. No....

Approved By: MM.Ma...549. Ve. Ve. No: 103/18-19.
The Building Committee 27/7/2018

Before starting any Construction the site must conform with the plans sanctioned and all theconditions as proposed in the plan should be fulfilled.

The validity of the written permission to execute the work is subject to the above conditions.

The sanction refers to the proposed portion shown in red and the Executive Engineers makes no admission as to the correctness of the plan.

Design of all Structural Members including that of the foundation should conform to Standards specified in the National Building Code of India

All Building Materials to necessary & construction should conform's to standered specified in the National Building Code of India.

Necessary steps should be taken

for the safety of the lives of the adjoining public and private properties during construction.

Non Commencement of Erection/ Re-Erection within Five year will Require Fresh Application for Sanction

DEVIATION WOULD MEAN DEMOLITION

RESIDENTIAL BUILDING

The first term of the first te

APPROVED

ON.04/12/22/9

A suitable pump has to be provided i.e. pumping unfiltered water for the distribution to the flushing cisterns and urinals in the building incase unfiltered water from street main is not available.

The building materials that will be stacked on Road/Passage or Foot-path beyond 3-months or after construction of G. Floor, whichever is earlier may be seized forthwith by the K.M.C. at the cost and risk of the owner.

Sanctioned subject to demolition
of existing structure to provide
open space as per plan before
construction is started

Executive Engineer (C)
BR. Asst. Engineer (C)
BR. Br. PLAN

No rain water pipe should be fixed or discharged on Road or Footpath.
Drainage plan should be submitted at the Borough Executive Engineer's Office and the sanction obtained before proceeding with the drainage work.

Any unathorised construction done in deviation from the Sanction Building permit and the Completion Plans after issuance of this Completion Plans may cause revocation of the Occupancy Certificate.

Sanctioned conditionally on an undertaking duly registered from the owner's to the effect till they will not evict any tenants & will also provide the tenants with identical area in and around the premises by mutual arrangements.

A. Preventive measures need to be taken for pollution free environment:

a) Wrap construction area/buildings with geotextile fabric installing dust barriers, or other actions, as eppropriate for the location.

b) Apply water and maintain soils in a visible damp or crusted condition for temporary stabilization.

c) Apply water and maintain soils in a visible earth moving activity to keep the soil moist throughout the process:

process;
d) Limit viricle speeds to 19 mph on the work size.
e) Clean wheels and undercarriage of haul trucks prior to leaving construction site.
e) Clean wheels and undercarriage of haul trucks prior to leaving construction of activity by water and Apply a cover or screen to stockpiles and stabilize stockpiles at completion of activity by water and Apply a cover or screen to stockpiles and stabilize stockpiles;
maintain a dust palliative to all outer surfaces of the stockpiles;
maintain surface soils where loaders, support equipment and vehicles will operate by using water and maintain surface soils in a stabilized condition where loaders, support equipment and vehicles will operate;
i) Stabilize adjacent disturbed soils following paving activities with immediate landscaping activity or installation of vegetative or rock cover.
ii) Stabilize adjacent disturbed soils following paving activities with immediate landscaping activity or installation of vegetative or rock cover.
ii) Maintain d. Control during working hours and clean track out from paved surfaces at the end of the work sid. Track out must now extend 50 feet or more and must be cleaned daily, at the minimum.

k) Stabilize stoping surfaces using soil binders until vegetation or ground cover can effectively stabilize.
the slope.
i) Disposal of debris in consultation with the local authorities following proper environmental management practice.
m) During construction work, including cutting of marbles, ambient noise level should not exceed more than 65 d8(A).

B. Practicus to be discarded for pollution free Environment:- .

Don't dispose of debris indiscriminately,

Don't allow the vehicles to run at high speed within the work site.

Don't cut materials without proper dust control/noise control facility.

Don't keep materials without effective cover.

Don't allow access in the work area except workers to limit soil disturbance and prevent access by fencing, ditches, vegetation, berms or other suitable barrier.

Don't linave the soil, sand and cement stack uncovered.

Don't keep materials or debris on the roads or pavements.

Don't keep materials or debris on the roads or pavements.

Burning of old tyres in hot mix plant as a fuel during construction and repair of the roads for melting coal far should be discarded:

Executive English Caren.
The Kolkulu Municipal Caren.
Building Department, Br.-X