

Schedule D

[Specifications, Amenities, Facilities of the Office Unit]

FOUNDATION: RCC Pile Foundation.

STRUCTURE: Earthquake resistant Reinforced Concrete Cement (RCC) framed structure with seismic compliance as per IS Code.

ELEVATORS: Two Automatic Lifts.

SERVICE ELEVATOR: One Automatic Lift.

FLOORING:

- ☒ Ground Floor Lobby - Imported Marble
- ☒ Units - Vitrified Tiles.
- ☒ Toilets - Antiskid Vitrified Tiles.
- ☒ Roof - Antiskid Vitrified Tiles.
- ☒ Stair Case- Granite/Kota Stone

DOORS & WINDOWS :-

- **UNIT MAIN DOOR :** Electronic Rolling Shutter.
- **WINDOWS:** Windows matching with the elevation.

WALL FINISH AND INTERIORS:-

- ☒ Gypsum Plaster finish on all interior walls.
- ☒ Common areas will be painted with Acrylic Emulsion Paint.
- ☒ All floor lobbies to be finished with decorative ceiling and imported Italian Marble Flooring and Granite paneled lift façade.
- ☒ Anti-termite, treatment on land and building plinth.

ELECTRICAL:

- ☒ Concealed copper wiring till main DB with premium quality MCB's.

STORE :

- ☒ Water line.
- ☒ Exhaust fans.

BATHROOM :-

- ☒ Vitrified tiles upto False Ceiling Height.
- ☒ Fittings in all the bathrooms.

- ☐ Light coloured or equivalent sanitary ware.
- ☐ Exhaust fans in bathrooms.
- ☐ Water proofing.

GENERAL FACILITIES:-

- ☐ Intercom facility in each unit with closed circuit T.V. for communication between main lobby, gate and units.
- ☐ DTH/Cable connection in all units.
- ☐ Modern Fire fighting equipments as per recommendations of WBF&ES.
- ☐ 100% Power Back-up for common areas and facilities.
- ☐ Main lobby at the ground floor to be air-conditioned
- ☐ Water and Heat proofing of the roof and finished with roof tiles.
- ☐ Deep Tube-well and corporation supply with adequate UG reservoir for drinking and fire fighting water along with iron removal and water softener plant.
- ☐ Driveway – Greenery, flowerpots/creepers. Floors with beautiful paver tiles.
- ☐ Decorative Boundary wall as per specification of the Architect

POWER SUPPLY & BACK UP:

- ☐ CESC HT / LT deposits, cabling charges and transformer charges to be paid by respective Office Unit Acquirers.
- 100% power back up at extra cost as per the requirement of the Office Unit Acquirers.

SUBIR UDYOG LIMITED
[Handwritten Signature]
Director/Authorised Signatory