

FRONT (WEST SIDE) ELEVATION



SECTION AT – II



SECTION AT – JJ



GROUND FLOOR PLAN



TYPICAL FLOOR PLAN
(1ST TO 4TH FLOOR)



ROOF PLAN

- Before any requirement for construction building plinth, 4 cm level of ... etc. subject to the condition.
- Before starting any construction, the site must conform with the plans sanctioned and all the condition as proposed in the plan should be fulfilled.
- All building materials necessary for construction should conform to standard specified in the National Building Code of India.
- ... necessary steps should be taken for safety of lives of the adjoining public, pedestrian properties during construction.
- ... on site should be maintained to prevent mosquito breeding.
- ... structural members including that of the foundation, ... conform to standard specified in the N.B.C. of India.
- The sanction is valid for 3 years from date of sanctioning.
- Information required by the applicant in this end are- Commencement of work. Completion of structural work up to plinth. Completion of work.
- Rain water pipe should be fixed or discharged on flood or Footpath.
- The construction should be taken up and finished as per sanctioned plan under the supervision of qualified empanelled engineer.
- Construction of garbage vat, soak pit & waste water should be done by the owners.
- Any deviation of the sanctioned plan shall ... sanction.

Asstt. Engineer
South 24 Pgs. Z.P.

District Engineer
South 24 Pgs. Z.P.

Sanctioned should be obtained from the Kulerdhari Gram Panchayat

Assistant Engineer
South 24 Pgs. Z.P.

Chief Executive Officer
South 24 Pgs. Z.P.

Approved
24-11-17
Engineer
KULER DARI GRAM PANCHAYET
Bishnupur-I, South 24 Parganas

Authorised Signatory
Kuler Dari Gram Panchayet
South 24 Parganas

SPECIFICATIONS

1. R.C.C. FRAME STRUCTURE WITH CONC. GRADE 1:1.5:3.
2. 200 M.M. THK. EXTERNAL 125 & 75 M.M. THK. INTERNAL WALLS WITH 1:4 CEMENT MORTER JOINTS.
3. STEEL Z– SECTION WINDOWS.
4. CAST–IN–SITU MOSAIC FLOORING.
5. 1:6 & 1:4 CEMENT PLASTER ON INTERNAL WALLS AND CEILING RESPECTIVELY.
6. WATER PROOFING TREATMENT.
7. P.O.P. PUNNING ON INTERNAL WALLS & CEILING.

DOOR & WINDOW SCHEDULE

TYPE	SILL	LINTEL	SIZE	TYPE	SILL	LINTEL	SIZE
D	-	2100	1500X2100	W1	275	2100	1500X1825
D1	-	2100	1100X2100	W2	275	2100	3089X1825
D2	-	2100	900X2100	W3	275	2100	1800X1825
D3	-	2100	825X2100	W4	900	2100	900X1290
D4	-	2100	750X2100	WK	1050	2100	1950X1050
DW	-	2100	1500X2100	WK1	1050	2100	800X1050
				W5	900	2100	1800X1050
				W6	900	2100	900X1050
				V1	1200	2100	600X1900

CERTIFICATE OF OWNER

CERTIFIED THAT WE HAVE GONE THROUGH THE BUILDING RULES FOR R.G. ALSO UNDERTAKE TO ABIDE BY THOSE RULES DURING & AFTER CONSTRUCTION OF BUILDING

OJSS REALTY PVT. LTD.

Director/Authorised Signatory

SIGNATURE OF OWNER

CERTIFICATE OF ENGINEER

CERTIFIED THAT THE FOUNDATION & SUPER STRUCTURE OF THE BUILDING HAVE BEEN SO DESIGNED BY ME TO SAFE IN ALL RESPECT INCLUDING THE BEARING CAPACITY OF E.T.C.

THE LAND IS PHYSICALLY VERIFIED BY ME & I FOUND THAT IT IS NOT A TANK OR FILLED UP TANK. IT IS NOT A TANK OR FILLED UP TANK. IT IS SALI & SUITABLE FOR PROPOSED CONSTRUCTION.

RANJAN J. PARIKH
M.E.(Struct.), F.I.E., M.CIVIL
(CIVIL), M.S.E. (MALAYSIA), M.I.E.(I)
F.I.V.S., F.I.P.E., M.I.B.C.

SIGNATURE OF ENGINEER

Rajkumar Agrawal
B.Arch., M.I.A.
Member of Council of Architecture CA / 94 / 17940

SIGNATURE OF L.B.A./L.B.S.

TITLE — BLOCK – 5

GROUND FLOOR PLAN, TYPICAL FLOOR PLAN (1ST TO 4TH FLOOR), ROOF PLAN, FRONT (WEST SIDE) ELEVATION, SECTION AT – II, SECTION AT – JJ.

PROJECT

PROPOSED G + IV STORIED RESIDENTIAL BUILDINGS PLAN (HEIGHT 15 METERS) ON PART OF R.S.& L.R. DAG NOS. 2, 4 & 14 AT MOUZA DAULATPUR, PARGANA – KHASPUR, R.S. NO. 341, J.L.: NO. 79 L.R. KHATIAN NO. 3196, P.S. BISHNUPUR UNDER KULERDHARI GRAM PANCHAYET, DISTRICT: SOUTH 24 PGS

OWNER'S–OJSS REALTY PVT. LTD

RAJ AGRAWAL & ASSOCIATES
ARCHITECTS,PLANNERS AND INTERIOR DESIGNERS
86, ROYD STREET (2ND FLOOR), KOLKATA - 16.

DATE: 18.01.17	DRAFT / SHEETS	CHECKED	REV. DATE	SHEET NO.
SCALE : 1:100	JOB NO. ARCH/16/2017			06 OF 06