

PARTY'S COPY

APPROVED FOR CONSTRUCTION

Any unauthorized construction done in deviation from approved building plan, after issuance of this permission, will warrant revocation of the construction permission.

STRUCTURAL DRAWINGS, STRUCTURAL DESIGN CALCULATIONS & SOIL TEST REPORT ARE NOT CHECKED AND KEPT FOR RECORDS ONLY.

LEVEL OF TOP OF THE BOX-DRAIN AND LEVEL OF EXIT/ ENTRY ALONG THE PROPERTY LINE OF ANY PLOT SHOULD BE AT PAR, THE ENTRY & EXIT SHOULD BE MADE WITH TEMPORARY TYPE OF CONSTRUCTION, LIKE PAVERS BLOCK OR EQUIVALENT.

VALID FOR 5 YEARS

NEW TOWN KOLKATA DEVELOPMENT AUTHORITY
Sanction of Building Plan for Construction Purpose

No. and date: 05 - Jan - 2018


PIN: 0060060720171220

Building Particulars G₁ + IX storied Residential Building
Area :- 06 - 0607



SUKRIT CHATTERJEE
Chief Architect

New Town Kolkata Development Authority



GROUND FLOOR PLAN
SCALE - 1:100

- NOTES:**
1. Top slab of the underground RCC reservoir under the driveway/parking will be structurally safe for carrying the load of heavy vehicles like fire tenders.
 2. Inlet / supply pipe to the underground water reservoir should be laid in such a way that it fills the Fire Tank first, then overflows to fill the domestic tank.
 3. The fire water reservoir shall have overflow arrangement with the domestic water reservoir to avoid stagnancy of water. The fire water reservoir shall be kept full at all times.

Area Statement

| | |
|---|------------------------------|
| Area of land: | 1512.00 sq.mt. (as per deed) |
| Abutting road width: | 20.0 MT. |
| Permissible F.A.R. | 2.49928 |
| Permissible Ground Coverage | 54.976% |
| Proposed Ground Coverage | 30.77% (465.26 SOM.) |
| AREA (DEDUCTED STAIRCASE, LIFT, DUCTS) | |
| Area As Per Sanctioned Plan | |
| Proposed covered area | In sq.mt. |
| Ground floor | 396.16 |
| First floor (RESIDENTIAL+MIXED) | 216.64+167.44=384.08 |
| Second floor | 407.14 |
| Third floor | 407.14 |
| Fourth floor | 407.14 |
| Fifth floor | 407.14 |
| Sixth floor | 407.14 |
| Seventh floor | 407.14 |
| Eighth floor | 407.14 |
| Ninth floor | 407.14 |
| TOTAL | 4037.36 |

- Deducted Area**
- 1) Staircase area for ground floor = $(16.58 \times 2) + 23.06 = 56.22$ sqmtr.
Staircase area for 1st floor = $(16.58 \times 2) + 23.06 = 56.22$ sqmtr.
Staircase area for 2nd to 9th each floor = $(16.58 \times 2) = 33.16$ sqmtr.
 - 2) Service Duct area = 0.50 sqmtr
 - 3) Lift well = $(2.24 \times 2) = 4.48$ sqmtr

- Exempted Service Area**
- 1) Caretaker's room + Toilet = 17.75 sqmtr (15 sqmtr. to be deducted for F.A.R.)
 - 2) Servant's room + Toilet = 18.29 sqmtr (15 sqmtr. to be deducted for F.A.R.)
 - 3) Service (Elec. Room + Fire Pump Room) = $(32.20 + 27.89) = 60.09$ sqmtr
Total service area for parking calculation = $(32.20 + 27.89 + 17.75 + 18.29) = 96.13$ sqmtr
Total service area for F.A.R. = $(32.20 + 27.89 + 15.00 + 15.00) = 90.09$ sqmtr
 - 4) Covered car parking area = 175.00 sqmtr


PARKING BUILT UP AREA = $4037.36 - (90.09 + 175.00)$ SQ.M. = 3766.23 SQ.M.
F.A.R BUILT UP AREA = $4037.36 - (90.09 + 175.00)$ SQ.M. = 3772.27 SQ.M.
F.A.R = $3772.27 / 1512.00 = 2.495$

Calculation of Parking


Residential Built-Up Area = $(3766.23 - 167.44)$ sqmtr = 3598.79 sqmtr
Require no. of parking (Cars) = $3598.79 / 100 = 35.98 = 36$
Assembly Built-Up Area = 167.44 sqmtr. (Business Use Area)
Require no. of parking = $(167.44 \times 1.2) / 100 = 2.01 = 2$

PARKING PROVIDED

| | |
|------------------|-----------------------------------|
| Open to sky | 24 nos |
| Partly covered | 14 nos |
| Fully covered | 14 nos |
| TOTAL | 38 nos |
| PROP. GREEN AREA | 60.88 sqmtr. (4.02% of land area) |




GROUND FLOOR PLAN
SCALE 1:50



DETAIL PLAN OF COLUMN FOUNDATION
SCALE-1:20

SECTION
SCALE-1:20



ENTRANCE GATE & FRONT SIDE BOUNDARY WALL
SCALE-1:50

PROJECT:
REVISED G+9 STORIED RESIDENTIAL BUILDING AT PREMISES NO. 06-0607 PLOT NO-AA-IIB/859/3 OF NEW TOWN, KOLKATA

APPLICANT & OWNER :
SERGEANT CO-OPERATIVE HOUSING SOCIETY LIMITED

- NOTES:**
1. ALL DIMENSIONS ARE IN MM.
 2. DISCREPANCIES IN DIMENSIONS OR OTHERWISE SHOULD BE BROUGHT TO THE NOTICE OF CONSULTANT BEFORE STARTING THE WORK.
 3. THIS DRAWING SUPERCEDES EARLIER DRAWINGS.
 4. ALL BRICKWORK PLASTERING INSIDE OR OUTSIDE ARE IN THE RATIO OF 1:6 & 1:4 RESPECTIVELY & OUTSIDE PLASTERING CONTAINS WATER PROOFING.
 5. THIS DRAWING SHOULD BE READ ONLY AND NOT TO BE SCALED.
 6. ALL CIVIL WORKS ARE AS PER I.S.456 AND ALL REINFORCEMENT AS PER I.S.1176
 7. ALL R.C.C. WORK SHOULD BE DONE AS PER SPECIFICATIONS MENTIONED IN THE STRUCTURAL DRAWINGS.
 8. ALL PRECAUTIONARY MEASURES SHALL BE TAKEN AT THE TIME OF CONSTRUCTION OF SEMI UNDERGROUND RESERVOIR.
 9. DEPTH OF WATER RESERVOIR SHALL NOT BE MORE THAN THE DEPTH OF MAIN COLUMN FOUNDATION.
 10. ALL EXTERNAL WALLS ARE 200 THK. AND ALL INTERNAL WALLS ARE 100 THK. UNLESS OTHERWISE SPECIFIED.
 11. THIS DRAWING SHOULD BE USED FOR SANCTION PURPOSE ONLY.
 12. LIFT DOORS SHALL BE F.C.D.
 13. ALL BALCONY & CHAJIA PROJECTIONS ARE 500 MM.

UNDERTAKING BY THE APPLICANT :

Kalyan Chakraborty

APPLICANT: Kalyan Chakraborty
ADDRESS : Gokhale Road Police Quarter, Kolkata-700020

CERTIFICATE OF THE ARCHITECT :

I CERTIFY THAT ALL THE ARCHITECTURAL DRAWING OF THE PROJECT AT PREMISES NO. 06-0607, PLOT NO. AA-IIB/859/3, HAVE BEEN PREPARED BY ME COMPLYING WITH THE NEW TOWN KOLKATA BUILDING RULES, 2009. I ALSO CERTIFY THAT THE PLANS AND DRAWINGS PREPARED BY ME COMPLY WITH ALL PROVISION REGARDING THE FIRE PROTECTION AS PER PREVAILING NATIONAL BUILDING CODE. I SHALL BE HELD RESPONSIBLE IF ANY INCORRECT INFORMATION IS FURNISHED BY ME OR ANY VIOLATION OF PROVISION OF THESE RULES OR THE PREVAILING NATIONAL BUILDING CODE IS FOUND IN ANY OF THE DRAWINGS AND DOCUMENTS, SIGNED BY ME AND SUBMITTED TO THE SANCTIONING AUTHORITY FOR OBTAINING SANCTION. POSITION OF DEPARTMENTAL MAN HOLE AT SITE IS BEING CERTIFIED BY ME ON VERIFICATION.

K. Bhatta

ARCHITECT: Konaditya Bhattacharjee
ENROLLMENT NUMBER: ARCH-HIDCO/09/00016

CERTIFICATE OF THE GEO-TECHNICAL ENGINEER :

IT IS CERTIFIED THAT THE COMPREHENSIVE GEO-TECHNICAL REPORT ON SOIL INVESTIGATION HAS BEEN PREPARED BY ME FOR DESIGN AND CALCULATION OF THE FOUNDATION BY ANALYSING THE SOIL SAMPLES FOR ESTIMATING THE BEARING CAPACITY OF THE SOIL ON WHICH FOUNDATION OF STRUCTURE WILL BE CONSTRUCTED.

I SHALL ALSO CHECK THE NATURE OF THE SOIL AFTER EXCAVATION AT SITE SO THAT FOUNDATION IS EXTENDED UP TO APPROPRIATE DEPTH THAT HAVE BEEN PROPOSED.

S. Sujit Kumar Bose

GEO-TECHNICAL ENGINEER: Dr. Sujit Kumar Bose
ENROLLMENT NUMBER: GTER-HIDCO/09/00004

CERTIFICATE OF THE STRUCTURAL ENGINEER :

CERTIFIED THAT THE STRUCTURAL DRAWING AND DESIGN OF BOTH THE FOUNDATION AND SUPERSTRUCTURE OF THE BUILDING/BUILDING HAS BEEN MADE CONSIDERING THE SOIL TEST REPORT (AS PER THESE RULES AND THE REGULATIONS MADE UNDER THE ACT) AND ALSO CONSIDERING ALL POSSIBLE LOADS, SEISMIC LOAD AND THE MOMENTS GENERATED BY THE PROPOSED STRUCTURE AS PER BUREAU OF INDIAN STANDARD AND NATIONAL BUILDING CODE OF INDIA AND CERTIFIED THAT IT IS SAFE AND STABLE IN ALL RESPECT AND THESE PROVISIONS SHALL BE ADHERED TO DURING THE CONSTRUCTION.

K. Sengupta

STRUCTURAL ENGINEER: Koushik Sengupta
ENROLLMENT NUMBER: STER/NKDA/10/00039

PURPOSE FOR MUNICIPAL SANCTIONED

ARCHITECTURAL DRAWING

GROUND FLOOR PLAN, 1ST FLOOR PLAN, ENTRANCE GATE & FRONT SIDE BOUNDARY WALL, AREA CALCULATIONS

SCALE: - 1:100, 1:1000 DRAWING NO. 2017/AR/SECHSL/SD/A/01 DATE 05/12/2017

CONSULTANT

aakriti ARCHITECTS O ENGINEERS O PLANNERS O LANDSCAPE DESIGNERS
12/1A Bosepukur Road, Kolkata - 700042

THIS DRAWING HAS NOT BEEN PUBLISHED AND IS THE SOLE PROPERTY OF AAKRITI AND IS ISSUED TO THE PARTY FOR THE SPECIFIC PURPOSE OF MUNICIPAL SANCTION AND IT SHALL NOT BE REPRODUCED, COPIED, LENT OR OTHERWISE DISPOSED OFF DIRECTLY OR INDIRECTLY, NOR USED FOR ANY OTHER PURPOSE OTHER THAN FOR WHICH IT IS FURNISHED.