

SCHEDULE- "G"

SI No	Item	Specifications	
1	Foundation	Isolated Footing	
2	Superstructure	RCC framed structure with first class traditional or flyash brick work	
3	Finishes		
	Bedrooms	Floor	Vitrified Tiles
		Floor	Kota stone/ Vitrified
	Kitchen	Counter	Polished Granite / Sadar Ali Grey Granite
		Sink	Stainless Steel
		Dado	Ceramic tiles above counter
	Toilet/s	Floor	Anti skid vitrified
Dado / Wall		Ceramic Tiles	
4	Doors	Main door	Flush door with Sal wood frame work
		Glass door	Clear toughened glass with powder coated aluminium frame work
		Internal door	Flush door with Sal wood frame work
5	Windows	Clear toughened glass with powder coated aluminium frame work	
6	Staircase	Kota Stone	
7	Sanitary ware	Wash Basin & WC	Hindware or equivalent
		Faucets	Hindware or equivalent
		Showerhead	Hindware or equivalent
8	Paint	Internal	POP punning over plaster
		External	Transparent water proof paint over brick clad surface & weather coat paint over plastered surface
9	Electrical	Concealed copper wiring, Plastic moulded switches	
10	Water Supply	Captive treated water supply through deep tube well	
11	Pipeline	Water Supply	UPVC
		Soil Pipe	UPVC
		Rain Water	PVC