Building specification

SCHEDULE- "G"

	Foundation		strip foundation
	Superstructure		'rcc framed structure with
			230 Brick work and sloped roof'
	Finishes		
	Bed rooms	Floor	vitrified tile
	Living/dining		
	Toilet	Floor	vitrified tile
		Dado	washable paint & ceramic tile
	Kitchen	Floor	granite
		Dado	granite,2ft above counter
	Deck		grey granite & paver tile
	Terrace		grey kota slab
	Staircase		trade-wooden
			Riser-vitrified tile
4	Door	Frame	sal
		Shutter	flush door
		Fittings	powder coated
		Paint	polish/duco paint finish
5	Window		powder coated aluminium glazed window
		Fittings	powder coated
6	Paint	Internal	pop finish
		External	weather coat
7	Electrical		concealed copper wiring
			Plastic modular switches
8	Water supply .		captive treated water supply through deep tube well
9	Pipeline	Water supply	upvc
		Soil pipe	ci pipe
		Rain water	pvc
10	Sanitaryware	Wash basin &wc	hindware
		Faucets	
		Showerhead	