TECHNICAL SPECIFICATION AND AMENITIES

PROJECT: Eden Tolly Signature Plus,344/1 Mahatma Gandhi Road,Kolkata-700104

Specification of Materials

Cement: Ordinary portland cement shall be used. Rapid hardening cement may be used if compelled by condition of availability, only under strict supervision ensuring effective casting and mechanical consolidation within fifteen minutes from delivery of the mix by the mixing machine.

Sand: Coarse sand, free from clay and all other foreign matters shall be used. Screening and washing arrangement are to be kept at site for use with sands containing impurities & intolerable properties.

Coarse Aggregates: Properly graded mixes of stone chips are to be used. The material shall be hard, homogeneous, free from pores, flakes and deleterious impurities. The material should not contain any sulphate and should not absorb more than 10% of its own weight of water. Maximum size of aggregate may be 25 mm. in beams, slabs and staircases.

Water: Water shall be clean and free from deleterious impurities. Portable water shall be used for mixing and curing.

Reinforcement: Torsteel ribbed bars of tested quality are to be used. These should be clean and free from loose mill-scales, dust, loose rust, any coats of paints or oily material which may destroy or reduce bond.

Specification of Work

Earth work: The rate shall be deemed to provide for excavation in any soil and include all dewatering and slush – clearance and shoring, if any, is required. The contractor should satisfy himself as actual nature of soil and site conditions by personally visiting the site.

Materials: All materials shall be new & best of its kind and shall confirm to its specifications or equivalent. No materials shall be used in work without prior approval of the Architect. The contractor must submit samples of various materials to the Architect, for approval before ordering for supply.

Workmanship: All workmanship must be best of its respective kinds and shall confirm to the latest plactice and shall be subject to the approval of the Architect.

Storage: Materials shall be transported handled with care and shall enter site carefully to prevent any damage or deterioration.

Cement shall be stored in a dry water tight shed on an elevated platform in sacks not exceeding six bags in height. Reinforcement shall be stored free from contact with moist surfaces.

Structural Concrete Work: All concrete work shall be of controlled variety as per cl. 9.3.2. of I.S. 456 of 1978.

The selection, grading, clearing by sieves and by washing aggregate mixing, control of water cement ratio, pouring, mechanical vibration and manual compaction shall all be guided by the strictest vigilance of experienced supervisor.

Authorized S

Reinforcement Work: Tested, mild steel, torsteel bars shall be used and shall be cleaned from mill scales, rust, oil, grease or other harmful adherents and shall be cold bend to shapes and dimensions shown in the drawings, tied together with 20 gauge annealed wires closely and tightly to prevent displacement during casting. During casting all tools, plants and workmen will move on other elevated walkways without touching the reinforcement. Casting will not be started till all these arrangements are complete. It must be remembered that the position of reinforcement is of utmost importance and any displacement and disturbance is not desirable.

Form Work: The formwork shall conform to the shapes, lines and dimension shown in the drawings and be of strong, rigid and leak-proof construction. Timber shuttering will be rebated and jointed with polythene sheets covering the joints. The propping, staging, strutting and bracing will be done with materials of sufficient strength to withstand all static and dynamic loads, possible during such construction. Care is to be taken to see that the form work is not disturbed in the process.

S ripping time for different parts shall be as follows:

1) 2) 3) 4) 5)	Soffits of slabs (less than 3.5 M Span) Soffits of slabs (less than 4.5 M Span)	 24 hours 7 days 10 days 14 days
ا (د	Soffits of beams (less than 4.5 M Span)	 21 days

The props for supported spans are to be removed from mid-span towards supports and those for cantilever spans from cantilever towards supports.

Curing: The beams shall be kept continuously wet by spraying water from below. The columns wrapped with sack or hessian and kept wet continuously.

Earthen bands are to be made on the floor slabs for at least seven days. Curing shall be done upto 29 days but a little relaxation may be allowed. However, absolutely continuous wetting necessary for first 7 days.

Brckwork: Brick shall be first class well burnt, sound well shapped and of standard dimensions. The shall be immersed and soaked in water for two hours before use in the jobs.

Mortar shall be 1:6 cement sand for 200 mm and 1:4 for 125 mm partition walls. All walls shall be perfectly true and vertical laid with frogs upward, perfectly bonded, levelled and thoroughly cured with water for 7 days.

Plaster: The joints in brick or stone work shall be hacked to a depth of 12 mm the surface thoroughly cleaned wetted and concrete surface roughed, hacked cleaned and wetted.

The mortar shall be composed of 1:6 cement sand for internal plaster, 1:4 for external plaster and 1:3 for ceiling plaster. The average thickness shall be 18 mm for external plaster, 15 mm for internal plaster and 9 mm for ceiling plaster.

Surfaces shall be finished smoothed, edged and lines true to shape and thoroughly cured with water for 7 days. No extra consideration shall be paid for plastering in recess, jambs of doors, windows, columns, etc.

NORTECH PROPERTY PRIVATE LIMITED

Authorized Signatory

Specifications of General Building Work

(1) All external walls should be 250 mm including plastering.

(b) All internal partition walls should be of 125/75 mm including plaster.

(c) Plaster with mortar should be done on both sides of the walls and finally plaster of paris coating should be done on all the walls excepting exterior walls.

(i) Proper water treatment to be done in the Basement floor and retaining walls of the basement and all the toilets and on the terrace of the building.

e) Elevation of the building should be nicely decorated with natural stone and snowcem cement paint.

The G.I. pipe fittings should be of ISI standards.

g) Electrical switches, cables and other fittings and fixtures should be of ISI specifications.

h) In the ground floor Rolling Shutter of reputed brand should be provided for shops / showrooms / carparks.

Specification of Finishing Work in Building

Common areas & exterior of the building:

Exterior with paint by certified Nerolac / Asian Paints / Berger Applicator and other effects as

The common areas in front portion of the Ground floor shall be provided with granite marble / vitrified tile floorings. Putty finished walls.

Proper light arrangement in the Ground floor, lobby and drive ways in entrance to be provided.

Proper waterproofing and water discharge system to be made for Basement and ground floor. v)

Arrangement for local authority water supply to be made, with necessary pumping arrangement; to ensure 24 hours water supply by the builder at their cost.

Telephone wiring to be done in each flat for 1 No. of telephone. Master antenna and cable T.V. vi) connection and arrangement for intercom facility to be made on the proportionate cost of the Flat

Lift of standard make like OTIS / KONE /ADAMS etc. of adequate to be provided. vii)

Water reservoirs for corporation water to be provided for storing water in sufficient quantity at viii) developers cost.

Inside of Flat

Plaster of Paris coating to be made on walls. i)

Main gate to be provided with a Godrej/Hafele Lock & handle. ii)

Flush doors with good quality of lock to be provided for all other doors. iii)

Inside partitions as per sanction plans. iv)

Toilet fitting shall be of ISI standard of reputed brands like Hindware, Jaquar, Kohler, CERA etc. v) All fittings shall be of Hindware, Jaquar, Kohler, CERA or equivalent brand.

Marble / Vitrified Tile flooring shall be provided in the rooms, drawing rooms and other areas vi) excepting that in kitchen and toilet, where ceramic tiles on walls and vitrified / ceramic tiles in floor will be provided.

Electrical work

- Concealed Polycab/Havells/Mescab/RR Kabel* copper wiring with modular switches of Anchor i) Roma/Schneider Electric/ RR Kable/ Havells
- TV & Telephone points in master bedroom and living room. ii)
- Two Light Points, one Fan Point, two 5A points in all bedrooms iii)

One 15A Geyser point in all toilets iv)

One 15A & one 5A points, one 5A refrigerator point, and exhaust fan points in kitchen v)

One AC point in master bedroom vi)

Modern MCBs and Changeovers of Havells / HPL / Scheneider Electric. vii)

NORTECH PROPERTY PRIVATE LIMITED