[Specifications, Amenities, Facilities of the Office Unit]

FOUNDATION: RCC Pile Foundation.

STRUCTURE: Earthquake resistant Reinforced Concrete Cement (RCC) framed structure with seismic

compliance as per IS Code.

ELEVATORS: Two Automatic Lifts.

SERVICE ELEVATOR: One Automatic Lift.

FLOORING:

- Ground Floor Lobby Imported Marble
- Units Vitrified Tiles.
- Toilets Antiskid Vitrified Tiles.
- Roof Antiskid Vitrified Tiles.
- Stair Case- Granite/Kota Stone

DOORS &WINDOWS:-

- UNIT MAIN DOOR: Rolling Shutter.
- WINDOWS: Windows matching with the elevation.

WALL FINISH AND INTERIORS:-

- Gypsum Plaster finish on all interior walls.
- Common areas will be painted with Acrylic Emulsion Paint.
- All floor lobbies to be finished with decorative ceiling and imported Italian Marble Flooring and Granite paneled lift façade.
- Anti-termite, treatment on land and building plinth.

ELECTRICAL:

Concealed copper wiring till main DB with premium quality MCB's.

STORE:

- Water line.
- Exhaust fans.

BATHROOM :-

- Vitrified tiles upto False Ceiling Height.
- Fittings in all the bathrooms.
- Light coloured or equivalent sanitary ware.
- Exhaust fans in bathrooms.
- Water proofing.

GENERAL FACILITIES:-

- Intercom facility in each unit with closed circuit T.V. for communication between main lobby, gate and units.
- DTH/Cable connection in all units.
- Modern Fire fightingequipments as per recommendations of WBF&ES.
- 100% Power Back-up for common areas and facilities.
- Main lobby at the ground floor to be air-conditioned
- Water and Heat proofing of the roof and finished with roof tiles.
- Deep Tube-well and corporation supply with adequate UG reservoir for drinking and fire fighting water along with iron removal and water softener plant.
- Driveway Greenery, flowerpots/creepers. Floors with beautiful paver tiles.
- Decorative Boundary wall as per specification of the Architect

POWER SUPPLY & BACK UP:

- © CESC HT / LT deposits, cabling charges and transformer charges to be paid by respective Office Unit Acquirers.
- 100% power back up at extra cost as per the requirement of the Office Unit Acquirers.

PS GROUP REALTY PVT. LTD.

Ravi kumai Byzan Director