

**GOVERNMENT OF WEST BENGAL
OFFICE OF THE DIVISIONAL FIRE OFFICER
WEST BENGAL FIRE & EMERGENCY SERVICES**

Memo No : IND/WB/FES/20182019/39516

DATE: 06/03/2019

From :
The Divisional Fire Officer
Fire Prevention Wing,
West Bengal Fire & Emergency Services.

To :
M/S Nirbhay Infra Developers Represented by Sri Manish Rai & Partner
S.P Mukherjee Road, R.S Plot no. 958, Kh. no. 460, J.L no. 35, ward no. 41 under
A.M.C, P.S Asansol(S), Dist. Paschim Bardhaman.
Asansol F.S., Asansol PS (S),
Paschim Bardhaman - 713303 .

Sub :Fire Safety Recommendation for a proposed construction of G + 4 storied
building under group Residential at the premises no.- S.P Mukherjee Road, R.S Plot
no. 958, Kh. no. 460, J.L no. 35, ward no. 41 under A.M.C, P.S Asansol(S), Dist.
Paschim Bardhaman.PIN- 713303

This is in reference to your Application No. IND/WB/FES/20182019/39516,dated 06/03/2019,
regarding the Fire Safety Measure for a proposed construction of G + 4 storied building
under group Residential at the premises no.- S.P Mukherjee Road, R.S Plot no. 958, Kh. no.
460, J.L no. 35, ward no. 41 under A.M.C, P.S Asansol(S), Dist. Paschim Bardhaman.PIN-
713303.

The plan submitted by you was scrutinized and marked as found necessary from Fire Safety
point of view. In returning one set of plan with recommendation, this is issuing Fire Safety
Recommendation in favour of the aforesaid building subject to the compliance of the
following fire safety measure.

Recommendation:

1. 1)The whole construction of the proposed G+4 Residential building shall be carried
out/fulfil in accordance with the relevant building rule i.e NBC-IV and local authority.

NIRBHAY INFRA DEVELOPERS
Manish

Partner

- 2) The statutory open spaces surrounding the building as specified in National Building Code and local municipalities building rule and regulation, shall be free from any obstruction, projection etc and shall be open to sky at all times.
- 3) The interior finishing decoration like wall, ceiling shall be made with low flame spread materials confirming relevant IS specification.
- 4) Provision of ventilation at the central core-duct of the building shall be provided.
- 5) Arrangements shall have to be made for sealing all the vertical ducts by the materials of fire resisting capacity.
- 6) All electrical wiring shall be done in accordance with the National Electrical Codes.
- 7) The approach road shall be sufficiently strong to withstand the load of Fire engine weighing min. 20 M.T.
- 8) The width and height of the access gates into the premises shall not be less than 4.5 & 5 M. respectively.
- 9) At least 2(two) no's exists (min. Width 1.5m) or more in the form of door leading directly to the outside of the building or stairways shall be provided. All exits shall be free from obstruction.
- 10) 2(Two) no's enclosed type internal stair case having minimum Fire resisting capacity not less than 4 hrs., shall be provided as remote from each other as possible. The FCD at the entrance of the all stair cases as well as Lift lobby encloser having minimum Fire Resisting capacity shall be one hrs.
- 11) All internal stair case shall be extended from ground floor to terrace level except access to the basement shall be by a separate stair case. The slope of Ramp shall not exceed 1:10.
- 12) The wall of the lift enclose shall be at least 2hrs. Fire Resisting type. Collapsible gate shall not be permitted.
- 13) Opening in walls or floors, which are necessary to provided to allow passages of all building services like cables, electrical wirings, tele. Cables, plumbing pipes etc. Shall be protected by enclose in the form of ducts/shafts having a fire resistance not less than 2hrs. No gas piping, electrical panels shall be allowed in the stairway.
- 14) All landing of floor shall have floor indicating board as well as illuminated exit sign with arrow indicating way to the escape routes shall be provided at the suitable height from the floor level on the wall, which should comply with graphic requirements of the relevant Indian standard.
- 15) Staircase and Corridor lightning shall also be connected to alternative supply which may be provided battery continuously trickle charged from the electric main.
- 16) Rooms containing inflammable or other service equipment subject to possible explosion shall not be located directly under or adjacent of the building.
- 17) Terrace level water tank capa. 25000lts, for only Fire Fighting purpose with replenishing arrangement @1000lts/min. preferably from two different sources of water supply shall be, provided for fire fighting purpose. One electric and one diesel pump of mini. Capacity 1620LPM and one electric pump of capacity 180LPM shall be provided to supply requisite

NIRBHAY INFRA DEVELOPERS

M. Anil

Partner

water pressure to the rising main. •

18) Down Comer (dia100mm) with facilities of instantaneous type coupling in out let of every half landing of the stair and the system shall be such to deliver 2400lts/min of water at ground level

19) Provision of Hose Reel in conjunction with Wet Riser shall be made at each floor level confirming the relevant IS specification. The length of the hose reel should be such that no part of the protected floor is more than 6m. away from the nozzle, at the time of fully extended.

20) At least 2nos Water Co2, 2nos ABC type, 2no Carbon dioxide type Fire Extinguisher, Fire bucket shall be installed in suitable places of each floor.

21) Manually operated electrical fire alarm system, Smoke detector, Heat Detector shall be installed in the suitable place of floors.

22) Alternative power supply with the help of Diesel Generator shall have to made to provide power to Fire pump, escape lighting, fire alarm etc. in case of normal power supply failure.

23) No storage or use of combustible materials of any kind shall be allowed in any part of the building except as necessary for day to day work.

24) Fire Notice for Fire Fighting and evacuation from the building shall be prepared and be displayed at all vulnerable places of the building.

25) A crew of trained fire fighting personnel shall be deployed round the clock.

26) Mock drill shall be conducted time to time with all Teacher, staff, security and students.

27) Arrangement shall be made for regular checking, testing and proper maintenance of all the fire safety installation and equipments installed in the building to keep them in good working condition at all times.

28) To eliminate fire hazards, good housekeeping, both inside and outside of the building, shall be strictly maintained regularly. Mock fire and evacuation drill shall be carried out periodically.

Any deviation and changes the nature of the use of the building in respect of submitted plan drawing, without obtaining prior permission from the office, the FSR shall be treated cancelled.

2. 1)The whole construction of the proposed G+4 Residential building shall be carried out/fulfil in accordance with the relevant building rule i.e NBC-IV and local authority.

2)The statutory open spaces surrounding the building as specified in National Building Code and local municipalities building rule and regulation, shall be free from any obstruction, projection etc and shall be open to sky at all times.

3)The interior finishing decoration like wall, ceiling shall be made with low flame spread materials confirming relevant IS specification.

4) Provision of ventilation at the central core-duct of the building shall be provided.

5) Arrangements shall have to be made for sealing all the vertical ducts by the materials of fire resisting capacity.

- 6) All electrical wiring shall be done in accordance with the National Electrical Codes.
- 7) The approach road shall be sufficiently strong to withstand the load of Fire engine weighing min. 20 M.T.
- 8) The width and height of the access gates into the premises shall not be less than 4.5 & 5 M. respectively.
- 9) At least 2(two) no's exists (min. Width 1.5m) or more in the form of door leading directly to the outside of the building or stairways shall be provided. All exits shall be free from obstruction.
- 10) 2(Two) no's enclosed type internal stair case having minimum Fire resisting capacity not less than 4 hrs., shall be provided as remote from each other as possible. The FCD at the entrance of the all stair cases as well as Lift lobby enclosure having minimum Fire Resisting capacity shall be one hrs.
- 11) All internal stair case shall be extended from ground floor to terrace level except access to the basement shall be by a separate stair case. The slope of Ramp shall not exceed 1:10.
- 12) The wall of the lift enclosure shall be at least 2hrs. Fire Resisting type. Collapsible gate shall not be permitted.
- 13) Opening in walls or floors, which are necessary to provided to allow passages of all building services like cables, electrical wirings, tele. Cables, plumbing pipes etc. Shall be protected by enclosure in the form of ducts/shafts having a fire resistance not less than 2hrs. No gas piping, electrical panels shall be allowed in the stairway.
- 14) All landing of floor shall have floor indicating board as well as illuminated exit sign with arrow indicating way to the escape routes shall be provided at the suitable height from the floor level on the wall, which should comply with graphic requirements of the relevant Indian standard.
- 15) Staircase and Corridor lightning shall also be connected to alternative supply which may be provided battery continuously trickle charged from the electric main.
- 16) Rooms containing inflammable or other service equipment subject to possible explosion shall not be located directly under or adjacent of the building.
- 17) Terrace level water tank capa. 25000lts, for only Fire Fighting purpose with replenishing arrangement @1000lts/min. preferably from two different sources of water supply shall be provided for fire fighting purpose. One electric and one diesel pump of mini. Capacity 1620LPM and one electric pump of capacity 180LPM shall be provided to supply requisite water pressure to the rising main.
- 18) Down Comer (dia100mm) with facilities of instantaneous type coupling in out let of every half landing of the stair and the system shall be such to deliver 2400lts/min of water at ground level
- 19) Provision of Hose Reel in conjunction with Wet Riser shall be made at each floor level confirming the relevant IS specification. The length of the hose reel should be such that no part of the protected floor is more than 6m. away from the nozzle, at the time of fully extended.

- 20) At least 2nos Water Co2, 2nos ABC type, 2no Carbon dioxide type Fire Extinguisher, Fire bucket shall be installed in suitable places of each floor.
- 21) Manually operated electrical fire alarm system, Smoke detector, Heat Detector shall be installed in the suitable place of floors.
- 22) Alternative power supply with the help of Diesel Generator shall have to made to provide power to Fire pump, escape lighting, fire alarm etc. in case of normal power supply failure.
- 23) No storage or use of combustibile materials of any kind shall be allowed in any part of the building except as necessary for day to day work.
- 24) Fire Notice for Fire Fighting and evacuation from the building shall be prepared and be displayed at all vulnerable places of the building.
- 25) A crew of trained fire fighting personnel shall be deployed round the clock.
- 26) Mock drill shall be conducted time to time with all Teacher, staff, security and students.
- 27) Arrangement shall be made for regular checking, testing and proper maintenance of all the fire safety installation and equipments installed in the building to keep them in good working condition at all times.
- 28) To eliminate fire hazards, good housekeeping, both inside and outside of the building, shall be strictly maintained regularly. Mock fire and evacuation drill shall be carried out periodically.
- Any deviation and changes the nature of the use of the building in respect of submitted plan drawing, without obtaining prior permission from the office, the FSR shall be treated cancelled.

Divisional Fire Officer
West Bengal Fire & Emergency Services

NIRBHAY INFRA DEVELOPERS
Mauist
Partner

Signature valid
Digitally signed by NITAI
CHATTOPADHYAY
Date: 2019.03.06 17:02:59 IST