

COLUMN SCHEDULE (BLOCK-A)

GRADE OF CONCRETE - M20

2ND FLOOR TO ROOF LVL	4-20 TOR + 4-16 TOR	8-16 TOR	4-20 TOR + 4-16 TOR	8-16 TOR
FOUNDATION TO 2ND FLOOR	8-20 TOR	4-20 TOR + 4-16 TOR	4-20 TOR + 4-16 TOR	8-16 TOR
LINK DETAILS				
C/S OF COLUMN				
COL SIZE	250x450	250x450	250x450	250x450
LINK	8 @ 100CC UP TO 75 FROM BEAM SOFFIT & SLAB TOP & REST PORTION @ 200CC	8 @ 100CC UP TO 75 FROM BEAM SOFFIT & SLAB TOP & REST PORTION @ 200CC	8 @ 100CC UP TO 75 FROM BEAM SOFFIT & SLAB TOP & REST PORTION @ 200CC	8 @ 100CC UP TO 75 FROM BEAM SOFFIT & SLAB TOP & REST PORTION @ 200CC
COL MARKED	C1A, C2A, C3A, C4A, C5A, C6A, C7A, C8A, C9A, C10A	C1A, C2A, C3A, C4A, C5A, C6A, C7A, C8A, C9A, C10A	C1A, C2A, C3A, C4A, C5A, C6A, C7A, C8A, C9A, C10A	C1A, C2A, C3A, C4A, C5A, C6A, C7A, C8A, C9A, C10A

COLUMN SCHEDULE (BLOCK-B)

GRADE OF CONCRETE - M20

2ND FLOOR TO ROOF LVL	4-20 TOR + 4-16 TOR	8-16 TOR	8-16 TOR	4-20 TOR + 4-16 TOR	8-16 TOR
FOUNDATION TO 2ND FLOOR	8-20 TOR	4-20 TOR + 4-16 TOR	8-16 TOR	4-20 TOR + 4-16 TOR	8-16 TOR
LINK DETAILS					
C/S OF COLUMN					
COL SIZE	250x450	250x450	250x450	250x450	250x450
LINK	8 @ 100CC UP TO 75 FROM BEAM SOFFIT & SLAB TOP & REST PORTION @ 200CC	8 @ 100CC UP TO 75 FROM BEAM SOFFIT & SLAB TOP & REST PORTION @ 200CC	8 @ 100CC UP TO 75 FROM BEAM SOFFIT & SLAB TOP & REST PORTION @ 200CC	8 @ 100CC UP TO 75 FROM BEAM SOFFIT & SLAB TOP & REST PORTION @ 200CC	8 @ 100CC UP TO 75 FROM BEAM SOFFIT & SLAB TOP & REST PORTION @ 200CC
COL MARKED	C1B, C2B, C3B, C4B, C5B, C6B, C7B, C8B, C9B, C10B	C1B, C2B, C3B, C4B, C5B, C6B, C7B, C8B, C9B, C10B	C1B, C2B, C3B, C4B, C5B, C6B, C7B, C8B, C9B, C10B	C1B, C2B, C3B, C4B, C5B, C6B, C7B, C8B, C9B, C10B	C1B, C2B, C3B, C4B, C5B, C6B, C7B, C8B, C9B, C10B

COLUMN SCHEDULE (BLOCK-C)

GRADE OF CONCRETE - M20

2ND FLOOR TO ROOF LVL	4-20 TOR + 4-16 TOR	8-20 TOR	4-20 TOR + 4-16 TOR	8-16 TOR	8-16 TOR
FOUNDATION TO 2ND FLOOR	8-20 TOR	8-20 TOR	12-20 TOR	4-20 TOR + 4-16 TOR	8-16 TOR
LINK DETAILS					
C/S OF COLUMN					
COL SIZE	250x450	250x450	250x450	250x450	250x450
LINK	8 @ 100CC UP TO 75 FROM BEAM SOFFIT & SLAB TOP & REST PORTION @ 200CC	8 @ 100CC UP TO 75 FROM BEAM SOFFIT & SLAB TOP & REST PORTION @ 200CC	8 @ 100CC UP TO 75 FROM BEAM SOFFIT & SLAB TOP & REST PORTION @ 200CC	8 @ 100CC UP TO 75 FROM BEAM SOFFIT & SLAB TOP & REST PORTION @ 200CC	8 @ 100CC UP TO 75 FROM BEAM SOFFIT & SLAB TOP & REST PORTION @ 200CC
COL MARKED	C1C, C2C, C3C, C4C, C5C, C6C, C7C, C8C, C9C, C10C	C1C, C2C, C3C, C4C, C5C, C6C, C7C, C8C, C9C, C10C	C1C, C2C, C3C, C4C, C5C, C6C, C7C, C8C, C9C, C10C	C1C, C2C, C3C, C4C, C5C, C6C, C7C, C8C, C9C, C10C	C1C, C2C, C3C, C4C, C5C, C6C, C7C, C8C, C9C, C10C

BEAM SCHEDULE FOR BLOCK-A

GRADE OF CONCRETE - M20

BEAM MKD	BEAM SIZE		REINPT. AT SUPPT		REINPT. AT SPAN		STIRRUPS	
	WIDE	DEPTH	TOP	BOTTOM	TOP	BOTTOM	SUPPORT	SPAN
B1	250	400	4-16 T	2-16 B	2-16 T	4-16 B	8 T @ 100CC	8 T @ 200CC
B2	350	400	5-16 T	4-16 B	2-16 T	4-16 B	8 T @ 100CC	8 T @ 200CC
B3	250	400	2-16 T	2-16 B	2-16 T	4-16 B	8 T @ 100CC	8 T @ 200CC
B4	250	450	2-16 T	3-16 B	2-16 T	5-16 B	8 T @ 100CC	8 T @ 200CC
B5	250	400	3-16 T	2-16 B	3-16 T	2-16 B	8 T @ 100CC	8 T @ 200CC
B6	250	400	4-16 T	2-16 B	2-16 T	4-16 B	8 T @ 100CC	8 T @ 200CC

BEAM SCHEDULE FOR BLOCK-B

GRADE OF CONCRETE - M20

BEAM MKD	BEAM SIZE		REINPT. AT SUPPT		REINPT. AT SPAN		STIRRUPS	
	WIDE	DEPTH	TOP	BOTTOM	TOP	BOTTOM	SUPPORT	SPAN
B1	250	400	4-16 T	2-16 B	2-16 T	4-16 B	8 T @ 100CC	8 T @ 200CC
B2	250	400	5-16 T	4-16 B	2-16 T	4-16 B	8 T @ 100CC	8 T @ 200CC
B3	300	400	4-20 T	2-20 B	2-20 T	4-20 B	8 T @ 100CC	8 T @ 200CC
B4	250	400	2-16 T	2-16 B	2-16 T	4-16 B	8 T @ 100CC	8 T @ 200CC
B5	250	400	4-16 T	2-16 B	2-16 T	4-16 B	8 T @ 100CC	8 T @ 200CC

BEAM SCHEDULE FOR BLOCK-C

GRADE OF CONCRETE - M20

BEAM MKD	BEAM SIZE		REINPT. AT SUPPT		REINPT. AT SPAN		STIRRUPS	
	WIDE	DEPTH	TOP	BOTTOM	TOP	BOTTOM	SUPPORT	SPAN
B1	250	400	5-16 T	2-16 B	2-16 T	5-16 B	8 T @ 100CC	8 T @ 200CC
B2	250	400	4-16 T	4-16 B	2-16 T	4-16 B	8 T @ 100CC	8 T @ 200CC
B3	250	400	2-16 T	2-16 B	2-16 T	5-16 B	8 T @ 100CC	8 T @ 200CC
B4	250	400	4-16 T	2-16 B	2-16 T	3-16 B	8 T @ 100CC	8 T @ 200CC
B5	250	400	2-16 T	3-16 B	2-16 T	5-16 B	8 T @ 100CC	8 T @ 200CC
B6	250	400	4-16 T	2-16 B	2-16 T	4-16 B	8 T @ 100CC	8 T @ 200CC

SCHEDULE OF FLOOR AND ROOF SLAB(BL-A)





PANEL MKD	REINFORCEMENT IN SHORTER DIRECTION	REINFORCEMENT IN LONGER DIRECTION
S1(115 TK)	8 TOR @ 100 C/C (Top) 8 TOR @ 125 C/C (Bot)	8 TOR @ 125 C/C (Top) 8 TOR @ 150 C/C (Bot)
S2(115 TK)	8 TOR @ 150 C/C (Top) 8 TOR @ 175 C/C (Bot)	8 TOR @ 175 C/C (Top) 8 TOR @ 200 C/C (Bot)
S3(115 TK)	8 TOR @ 125 C/C (Top) 8 TOR @ 150 C/C (Bot)	8 TOR @ 150 C/C (Top) 8 TOR @ 200 C/C (Bot)
S4(115 TK)	8 TOR @ 200 C/C (Top) 8 TOR @ 100 C/C (Bot)	8 TOR @ 200 C/C (Top) 8 TOR @ 200 C/C (Bot)

SCHEDULE OF FLOOR AND ROOF SLAB(BL-B)

PANEL MKD	REINFORCEMENT IN SHORTER DIRECTION	REINFORCEMENT IN LONGER DIRECTION
S1(115 TK)	8 TOR @ 125 C/C (Top) 8 TOR @ 150 C/C (Bot)	8 TOR @ 150 C/C (Top) 8 TOR @ 175 C/C (Bot)
S2(115 TK)	8 TOR @ 150 C/C (Top) 8 TOR @ 175 C/C (Bot)	8 TOR @ 200 C/C (Top) 8 TOR @ 200 C/C (Bot)
S3(125 TK)	8 TOR @ 100 C/C (Top) 8 TOR @ 125 C/C (Bot)	8 TOR @ 125 C/C (Top) 8 TOR @ 150 C/C (Bot)
S4(115 TK)	8 TOR @ 150 C/C (Top) 8 TOR @ 175 C/C (Bot)	8 TOR @ 150 C/C (Top) 8 TOR @ 175 C/C (Bot)

SCHEDULE OF FLOOR AND ROOF SLAB(BL-C)

PANEL MKD	REINFORCEMENT IN SHORTER DIRECTION	REINFORCEMENT IN LONGER DIRECTION
S1(115 TK)	8 TOR @ 150 C/C (Top) 8 TOR @ 175 C/C (Bot)	8 TOR @ 175 C/C (Top) 8 TOR @ 200 C/C (Bot)
S2(115 TK)	8 TOR @ 125 C/C (Top) 8 TOR @ 150 C/C (Bot)	8 TOR @ 150 C/C (Top) 8 TOR @ 175 C/C (Bot)
S3(125 TK)	8 TOR @ 175 C/C (Top) 8 TOR @ 200 C/C (Bot)	8 TOR @ 200 C/C (Top) 8 TOR @ 200 C/C (Bot)
S4(115 TK)	8 TOR @ 200 C/C (Top) 8 TOR @ 100 C/C (Bot)	8 TOR @ 200 C/C (Top) 8 TOR @ 200 C/C (Bot)



AREA STATEMENT

TOTAL AREA OF LAND (PER DEED) 114K-070H-27SET-968.24 SQM	
TOTAL AREA OF LAND (PER MEASURED)	= 968.24 SQM
PERMISSIBLE COVERED AREA (50%)	= 484.12 SQM
(BLOCK-A) COVERED AREA - GROUND FLOOR (GARAGE) = 184.54 SQM	
1ST FLOOR	= 184.54 SQM
2ND FLOOR	= 184.54 SQM
3RD FLOOR	= 184.54 SQM
(BLOCK-A) TOTAL COVERED AREA	= 738.16 SQM
(BLOCK-B) COVERED AREA - GROUND FLOOR = 205.86 SQM	
1ST FLOOR	= 205.86 SQM
2ND FLOOR	= 205.86 SQM
3RD FLOOR	= 205.86 SQM
(BLOCK-B) TOTAL COVERED AREA	= 823.44 SQM
CAR PARKING AREA (OUT OF GROUND FLOOR) = 117.09 SQM	
FLAT AREA (50% OVER GROUND FLOOR)	= 88.77 SQM
(BLOCK-C) COVERED AREA - GROUND FLOOR = 198.52 SQM	
1ST FLOOR	= 198.52 SQM
2ND FLOOR	= 198.52 SQM
3RD FLOOR	= 198.52 SQM
CAR PARKING AREA (OUT OF GROUND FLOOR) = 110.32 SQM	
FLAT AREA (50% OVER GROUND FLOOR)	= 88.20 SQM
(BLOCK-C) TOTAL COVERED AREA	= 794.08 SQM
(BLOCK-A+B+C) TOTAL COVERED AREA	= 2355.68 SQM
LEFT OPEN AREA	= 372.52 SQM
VOLUME OF TOTAL CONSTRUCTION	= 7281.275 SQM

PROPOSED IV STORED RESIDENTIAL BUILDING PLAN OF SMT. MANJULA BHATTACHARYA & OTHERS, IN RESPECT OF MUNICIPAL HOLDING NO.- 50, SARAT BOSE ROAD, WARD NO.- 06, MOUZA- DIGLA, JL. NO.- 18, R.S. NO.- 161, TOUZI NO.- 173, C.S. & R.S. KHATIAN NO.- 270, 271, 589, 590, C.S. & R.S. DAG NO.- 569, 570, P.S. DUM DUM, DIST.- 24 PGS (N), UNDER SOUTH DUM DUM MUNICIPALITY.

- NOTE:-**
- ALL DIMENSIONS ARE IN MM UNLESS OTHERWISE MENTIONED.
 - ANY AMBIGUITY IN THE DRAWING SHOULD BE IMMEDIATELY BROUGHT TO THE NOTICE OF THE CONSULTANT BEFORE COMMENCING WORK.
 - SUPER STRUCTURE: SUPER STRUCTURE SHALL BE OF 1ST CLASS BRICK IN 1:6 CEMENT MORTAR.
 - THIS DRAWING IS TO BE READ ALONG WITH ALL RELEVANT ARCHITECTURAL DRAWINGS.
 - ALL GRADE OF CONCRETE SHALL UNLESS OTHERWISE NOTED.
 - ALL MATERIALS SHALL CONFORM TO RELEVANT IS CODES.
 - FOR STEEL GRADE IS 500 AS PER IS 1786-2008.
 - ALL DISTRIBUTION TRAYS ARE TO BE 250 C/C AND TO BE PROVIDED.
 - ALL CHAIRS ARE TO BE PROVIDED WHEREVER REQUIRED.
 - ALL SPACER BARS ARE TO BE 250 C/C AND TO BE PROVIDED.
 - LAPS, SPLICES & BOND LENGTH SHOULD BE 50 D WHERE 'D' IS DIA OF BAR.
 - FOUNDATION & FINISH BY WORK IN FOUNDATION & FINISH SHALL BE OF 1ST CLASS IN 1:6 CEMENT MORTAR.
 - MINIMUM CLEAR COVER TO MAIN REINFORCEMENT IS AS FOLLOWS:
- | MEMBER | TOP | BOTTOM | SIZE |
|------------|-----|--------|------|
| PILE | 50 | 50 | 50 |
| PILE CAP | 75 | 75 | 75 |
| COLUMN | 40 | 40 | 40 |
| FLOOR BEAM | 30 | 30 | 30 |
| ROOF BEAM | 30 | 30 | 30 |
| FLOOR SLAB | 20 | 20 | 20 |
- SPECIFIC GRAVITY OF THE CONCRETE SHALL BE MAINTAINED AT 1.25 TO 1.27 BEFORE CASTING.

CERTIFICATE OF OWNER

CERTIFIED THAT I SHALL NOT ON A LATER DATE MAKE ANY ADDITION & ALTERATION TO THIS PLAN SO AS TO CONVERTER FOR USE OR ALLOW IT TO BE USED FOR DIFFERENT PLANS PER FLOOR/STORY.

CERTIFIED THAT I HAVE GONE THROUGH THE BUILDING RULES FOR THE SOUTH DUM DUM MUNICIPALITY IN VOICE & ALSO INTEND TO ABIDE BY THOSE RULES DURING & AFTER CONSTRUCTION OF THE BUILDING.

CERTIFIED THAT I ALSO UNDERTAKE TO REPORT TO THE MUNICIPALITY 7 DAYS BEFORE COMPLETION WOULD BE REQUIRED WITHIN 10 DAYS.

I ALSO UNDERTAKE TO REPORT TO THE COURT CASE OR ANY COMPLAINT FROM ANY CORNER IN RESPECT OF THIS PROPERTY AS PER PLAN.

I HAVE NOT SOLD/TRANSFERRED ANY PART OF MY PROPERTY/LAND TO WHosoever UNTIL NOW.

IF ANY DISPUTE ARISES IN FUTURE SOUTH DUM DUM MUNICIPALITY WILL NOT BE LIABLE.

(Signature)
Support Das
Nandana Chatterjee
Dakshinapaul
Rajesh Choudhary
Signature
SIG. OF THE OWNER

CERTIFICATE OF ENGINEER

CERTIFIED THAT THE FOUNDATION & SUPER STRUCTURE OF THE BUILDING HAVE BEEN SO DESIGN BY ME/AS PER SAFE IN ALL RESPECT INCLUDING THE CONSIDERATION OF BEARING CAPACITY & SETTLEMENT OF SOIL ETC AS PER I.S. STANDARD & B.R. CODE.

CERTIFIED THAT THE PLAN HAS BEEN DRAWN UP STRICTLY ACCORDING TO THE BUILDING RULES FOR SOUTH DUM DUM MUNICIPALITY.

I AS A STRUCTURAL DESIGNER HEREBY CERTIFY THAT I OWNED SOUTH DUM DUM MUNICIPALITY FOR ANY STRUCTURAL DEFECTS AND / OR FAILURE OF THE PROPOSED BUILDING AFTER OR DURING THE CONSTRUCTION.

HOWEVER STRUCTURAL DESIGN DEFECTS ARE SUBMITTED FOR REFERENCE OF MUNICIPALITY.

(Signature)
MS. MITA SAHA
M.E. (Struct), MIE, CE
REGD. No. 50461, Dist. Lab.
Dist. No. 081886112

MITA SAHA
Licensed Building Surveyor
Class Lic No. SODM/S 5177

SIG. OF THE LRS

SIG. OF THE ENGINEER

STRUCTURAL CONSULTANT DRAWN BY: CHECKED BY: MITA SAHA
S. Adhikary

MAK ENGINEERS
San-Lake City,
B/224, Sector-1,
Kulaba-700 064
E-mail: makengr@rediffmail.com
Mob. no. - 9881788112

SCALE - 1:100

DATE - 06.09.2018

SHEET - 2 OF 2