Latitude: 22.587473 N
Longitude: 88.497395 E



GROUND FLOOR PLAN
SCALE:- 1:100

AREA STATEMENT:-

AREA OF PLOT (AS PER DEC.)	= 1618.73 SQ.M.
AREA OF PLOT (AS PER PHYSICAL)	= 1400.55 SQ.M.
PERMISSIBLE F.A.R.	= 2.0
PERMISSIBLE BUILT UP AREA (1400.55*2.0)	= 2801.1 SQ.M.
PROPOSED BUILDING HT.	= G+IV
PERMISSIBLE GROUND COVERAGE (50%)	= 700.275 SQ.M.
PROPOSED GROUND COVERAGE (48.687%)	= 679.00 SQ.M.
PROPOSED GROUND FLOOR AREA	= 607.30 SQ.M.
PROPOSED TYPICAL(1ST TO 4TH) FLOOR AREA	= 635.80 SQ.M.
PROPOSED TOTAL FLOOR AREA (607.3+635.80*4)	= 3210.06 SQ.M.
PROPOSED TOTAL WARDROBE AREA	=56.0 SQ.M.

EXEMPTION

RESIDENTIAL STAIR AREA (12.69*5 FLS.)	= 63.45 SQ.M.
LIFT LOBBY AREA (6.8*5 FLS.)	= 30.0 SQ.M.
CAR PARKING AREA AT GROUND FLOOR	= 463.96 SQ.M.
TOTAL EXEMPTION AREA (63.45+30.0+463.96)	= 557.31 SQ.M.
PROPOSED TOTAL FLOOR AREA AFTER EXEMPTION (3210.06-557.31)	= 2652.75 SQ.M.
PROPOSED FAR (2652.75/1400.55)	= 1.894

FLAT DETAIL (PROPOSED)

2BHK	=7*4 FLS.	= 28 NOS.
3BHK	=2*4 FLS.	= 08 NOS.
	TOTAL NO OF FLAT=	36 NOS.
TOTAL NO OF USERS (36 FLATS @ 5 PERSON)		=180 NOS.

CAR PARKING CALCULATION

COMMERCIAL	
SHOP AREA AT GROUND FLOOR	=83.71 SQM.
NO. OF CARS REQUIRED	=01 NOS.
RESIDENTIAL	
FLAT AREA 75 TO 100 SQ.M.	=36 NOS.
REQUIRED NO. OF CARS	=18 NOS.
TOTAL NOS. OF CARS REQUIRED (1+18)	=19 NOS.
TOTAL NOS. OF CARS PROVIDED (COVERED=24 & OPEN=4)	=28 NOS.

TYPICAL FLAT AREA CHART OF EACH FLOOR

FLAT NOS.	FLAT TYP.	FLAT BUILT UP AREA (SQ.M.)	NOS.
A	2 BHK	83.61	4
B	2 BHK	90.03	4
C	2 BHK	89.04	4
D	2 BHK	89.24	4
E	2 BHK	89.24	4
F	2 BHK	88.88	4
G	2 BHK	90.02	4
H	3 BHK	99.67	4
I	2 BHK	89.47	4

SCHEDULE OF DOORS & WINDOWS

TYPE	SIZE	NOS.	TYPE	SIZE	NOS.	TYPE	SIZE
D1	750*2100	04	W1	1200*1200	04	V1	600*600
D2	900*2100	04	W2	1500*1200	02	V2	600*900
D3	750*2100	02	W3	1800*1200	02	V3	600*1200
D4	900*2100	04	W4	900*1200	04	V4	600*600
D5	750*2100	04	W5	600*1200	04	V5	1200*600
D6	750*2100	02	W6	1200*1200	02	V6	1200*600
			W7	1200*1200	02	V7	600*600

SPECIFICATION OF BUILDING

1. ALL DIMENSIONS ARE IN M.M.
2. 1ST CLASS CEMENT BRICK WORK IN RAICH STRUCTURE.
3. TESTS ON THE 1ST CLASS BRICK WORK TO BE MIX R.C.C. WORK.
4. 1:2:4 CONC. 1:2:4 RCC. IN RAB. SLOPE CONCRETE.
5. R.C.C. WORK FOR BEAM, SLAB, LINTEL, SUNSHADE ETC.
6. CEMENT MORTAR PLASTER TO RAB. PVC. IN OUTSIDE & BRICK WALLS OF 12 M.M. & 6 M.M. THK. IN CEILING & RCC. CHAJJA.
7. IN ALL RM. 4'-0" FLOORING WITH ANTI SKID CERAMIC OF TOP WELL SHINING.
8. 4 INCH RCC CASING IN FLOORING & FOUNDATION.
9. ALL STEEL I BARS FOR COLUMNS, BEAMS, LINTELS & SLABS INCLUDING DISTRIBUTERS & BINDERS.
10. NOT A LANDING FOR SANCTIONING OF PLAN. WORKS INCLUDING STEEL PROFILES TO BE PLACED AS PER DIRECTION.
11. CONCRETE & PLASTERING, FITTING & FIXING COMPLETE AS PER DIRECTION.
12. ALL OUTSIDE WALLS 250 MM. THK. & INSIDE WALL 125 & 75 MM. THK. OF CLASS BRICK WITH BEST MORTAR IN EVERY 3RD LAYER.

SIGNATURE OF OWNER

(I/WE CONFIRM THAT THE ERECTION OF BUILDING TO BE UNDERTAKEN SHALL BE STRICTLY IN ACCORDANCE WITH THE NEW PLANNING AREA NOT WITH AND THE RULES MADE THERE UNDER)

SIGN. OF OWNER

CERTIFICATE OF ARCHITECT

I CERTIFY THAT ALL THE ARCHITECTURAL DRAWINGS OF THE PROJECT AT 11, NO. -32, DAG NOS. -1610, 1611 KHATIAN NOS. - 5665, 5666, 5667, 5683, 5684, 5685, 5686, 5687, 5688 MOUZA - MUHAMMAD PUR, UNDER RAJARHAT - BISHNUPUR NO - 1 GRAM PANCHAYET RAJARHAT, DIST. - NORTH 24 PARGANAS, HAVE BEEN PREPARED BY ME COMPLYING WITH THE NEW TOWN KOLKATA PLANNING AREA (DEVELOPING RULES), 2014 / BUSS (2009) THAT THE PLANS AND DRAWINGS PROPOSED BY ME COMPLYING WITH ALL THE PROVISIONS INCLUDING THE FIRE PROTECTION AS PER THE PREVAILING NATIONAL BUILDING CODE OF INDIA. I SHALL BE HELD RESPONSIBLE IF ANY INCORRECT INFORMATION IS FURNISHED BY ME OR ANY VIOLATION OF PROVISIONS OF THESE RULES OF THE PREVAILING NATIONAL BUILDING CODE IS FOUND IN ANY OF THE DRAWINGS AND DOCUMENTS, SIGNED BY ME AND SUBMITTED TO THE SANCTIONING AUTHORITY FOR OBTAINING SANCTION.

Rakhmal Agarwal
Reg. No. of Council of Architects (No.) 17595

SIGN. OF ARCHITECT

I, IS HEREBY CERTIFIED THAT THE STRUCTURAL DRAWINGS ARE PREPARED FOR EARTHQUAKE RESISTANCE IN ACCORDANCE WITH BIS & NBC 2005.

SIGN. OF GEO-TECHNICAL ENGINEER

CERTIFICATE OF STRUCTURAL ENGINEER

CERTIFIED THAT, "THE STRUCTURAL DRAWING & DESIGN OF BOTH FOUNDATION & SUPER STRUCTURE OF THE BUILDING / BUILDINGS HAS BEEN MADE CONSIDERING THE SOIL TEST REPORT, AS PER THE RULES AND REGULATIONS MADE UNDER THE ACT AND ALSO CONSIDERING ALL POSSIBLE LOADS, SEISMIC LOAD AND THE MOMENTS GENERATED BY THE PROPOSED STRUCTURE AS PER THE BUREAU OF INDIAN STANDARD AND NATIONAL BUILDING CODE OF INDIA AND CERTIFIED THAT IT IS SAFE & STABLE IN ALL RESPECT AND THESE PROVISIONS SHALL BE ADHERED TO DURING THE CONSTRUCTION.

Mainak Majumder
A.C.P. No.C.E. (Struct)
B.E. - 1st Cl. of CSVTU
STRUCTURAL ENGINEER
01401/P/SDN/2021/11-12

SIGN. OF STRUCTURAL ENGINEER

TITLE

GROUND FLOOR PLAN, SITE PLAN, LOCATION PLAN, DETAIL OF SEPTIC TANK & DETAIL OF UNDER GROUND WATER HARVESTING.

PROJECT

PROPOSED G+IV STORIED (1439 SFT SFT.) RESIDENTIAL BUILDING AT- 11, NO. - 32, DAG NOS. - 1610, 1611 KHATIAN NOS. -5682, 5683, 5684, 5685, 5686, 5687, 5688 MOUZA - MUHAMMAD PUR, UNDER RAJARHAT - BISHNUPUR NO - 1 GRAM PANCHAYET RAJARHAT, DIST. - NORTH 24 PARGANAS.

DATE	JOB NO.	SEAT	CHECKED	SHEET NO.
23.06.17	MOU/RJB/2017	SHEET		01 OF 05

SCALE 1:50,100,1000

ARCHITECT

RAJ AGARWAL & ASSOCIATES

FOR OFFICE USE ONLY

SITE PLAN
SCALE:- 1:800



LOCATION PLAN
SCALE:- 1:4000



SECTION



SECTION Y-Y



N. U. G. W. H. FOR DOMESTIC
CAP:-12,000 LTS.
SCALE:-1:50



PLAN OF SEPTIC TANK
(150 USER)
SCALE:-1:50

Approved Plan No. BP/NCT
Date 8/11/17
Validity upto 8/11/22

The structural analysis reports & soil reports are kept for reference in this office. The clearance is accepted subject to certificate of architect, Gn. Engineer, Geo-Tech Engineer.

District Engineer
(N) 24 Parganas Zilla Parishad

SANCTIONED & APPROVED
10/11/18