

PROPOSED G+III STOREYED RESIDENTIAL/
COMMERCIAL BUILDING PLAN WITH SANITARY
SYSTEM OF 1) SMT MALATI SINHA W/O SRI RUN
KR. SINHA, 2) SMT MADHABI KAR W/O SRI SAMAR
KR. KAR, 3) SMT BULA DAS W/O SRI KYALAN KR
DAS, 4) SMT RITA CHAKRABORTY W/O SRI ASIM
KR. CHAKRABORTY AT MOUZA -SUKCHAR, J.L.
NO.-9, R.S. NO.- , TOUZI NO.- 156, KHATIAN NO.-
431, DAG NO.- 3322, WARD NO.- 2, HOLDING
NO.-26, ARABINDA PALLY, UNDER PANIHATI
MUNICIPALITY, P.S. - KHARDAH, DIST. -24 PGS(N).

NO OF FLAT - 6

AREA STATEMENT

TOTAL AREA OF LAND:- 3 K-6CH -25 SFT.(M/L)

PROP. GROUND FLOOR COV. AREA = 143.31 Sqm.
PROP. 1ST. TO 3RD. FLOOR COV. AREA=143.31X3Sqm.
TOTAL COV. AREA = 572 Sqm.

PROP. GROUND FLOOR CARPET AREA = 128.98 Sqm.
PROP. 1ST. TO 3RD. FLOOR COV. AREA = 128.98X3 Sqm.
TOTAL CARPET AREA = 515.92 Sqm.

ALL DIMENTION ARE IN MM

SPECIFICATIONS OF WORK

1. 75 TH PICKED BRICK SOLING IN FOUNDATION & FLOOR.
2. CEMENT CON. WILL BE 1:3:6 CEMENT, SAND & JHAMA.
3. R.C.C. WILL BE 1:2:4 CEM. SAND & 20mm DOWN STONE CHIPS.
4. 250 TH BRICK WORK WILL BE 1:6, CEMENT, SAND MORTAR.
5. 125 BRICK WORK WILL BE 1:5 CEMENT, SAND MORTAR.
6. 25 TH D.P.C. WILL BE 1:2:4 CEM SAND & 6mm DOWN STONE.
7. CEILING PLASTER WILL BE 1:4 CEM. SAND MORTAR 6mm TH.
8. IN SIDE PLASTER WILL BE 1:6 CEM. SAND MORTAR 19mm TH.
9. OUT SIDE PLASTER WILL BE 1:4 CEM SAND MORTAR 12mm TH.
10. ALL BUILDING MATERIALS WILL BE AS PER I.S. CODE & C.B.C. 1984.
11. GRADE OF CONC. M15, GRADE OF STEEL Fe415.
12. SCALE USED 1:100, 1:50, 1:200

SCHEDULE OF DOORS & WINDOWS